BOLTON INLAND WETLANDS COMMISSION REGULAR MEETING 7:00 P.M., TUESDAY, SEPTEMBER 23, 2025 VIRTUAL MEETING VIA ZOOM

Inland Wetlands Commission Members Present Via Zoom: Chair Ross Lally, Vice Chair James Loersch, Member Diane DeNunzio, Member Michael McDonnell. Absent was Member David Lynn.

Staff Present Via Zoom: Wetlands Agent Alyssa Barroso, Board Clerk Mary Johnston

Others Present Via Zoom: Paul Toomey, Stephen King, Barbara Knight, Ronald Bisson

1. Approval of Agenda

D. DeNunzio MOVED to approve the agenda. J. Loersch SECONDED the motion. MOTION CARRIED UNANIMOUSLY 4:0:0.

2. Public Comment

Stephen King, 90 Burnett Brook Road, Andover, stated he had reached out to the Town of Bolton on several occasions regarding dumping of debris in wetlands across the street of 34 Skinner Road, Bolton. A. Barroso stated the owner of the property has been dumping debris and the Town Administrator visited the site. A. Barroso stated she has issued a notice of violation to the property owner and requested a response by next Friday. S. King stated he does not trust the owner to clean up the property correctly.

3. Approval of Minutes

3a. August 26, 2025, Regular Meeting

J. Loersch MOVED to approve August 26, Regular Meeting Minutes. D. DeNunzio SECONDED. MOTION CARRIED 4:0:0.

4. Old Business

4a. IW-25-14: Ronald Bisson – 139 Vernon Rd – Cut & Remove Select Trees, Stumps & Shrub to Create View Corridor

A. Barroso reported she visited the site last week and met with R. Bisson. A. Barroso said an additional map with more details was provided showing which trees are being removed or staying and showing the distance from the waterline. A. Barroso said trees marked with pink will remain and trees marked with white will be removed. R. Bisson stated the removal equipment will be a mini escalator and all stumps to be removed. R. Bisson added the undergrowth will be removed and will add hydro seed. J. Towney stated this project is to manage the forest and not create a view corridor to the lake. J. Loersch expressed concerns of disturbance to the lake. R. Bisson replied hay bales will be placed in the lake and swaddles on the bank. M. McDonnell was concerned with hay bales in the lakebed. A. Barroso added the work near the lake will be done when the lake is drawn down. R. Lally stated he was concerned with the lack of notes on the map showing proposed work and

requested more details/notes on the map. After discussion, M. McDonnell MOVED to issue a conditional permit with the inclusion of a legend which identifies the location of the trees on the plan with a letter corresponding to a picture of that said tree attached as part of the permit and secondly to modify the note concerning the hay bales placed in the lake add to it by completion of the project the hay bales and any sediment collected behind the hay bales will be removed at the end of the project and prior to the lake coming back up. J. Loersch SECONDED the motion. M. McDonnell AMENDED his motion to include the color coding of the trees marked with red and work will begin after the lake is drawn down and completed before water is brought back up. J. Loersch SECONDED the amendment. MOTION CARRIED UNANIMOUSLY 4:0:0 AS AMENDED.

4b. IW-25-13: Jordan Knight – **51 Loomis Rd** – **New Construction of a 2-Family Dwelling** A. Barroso reviewed the revised plan showing the requests that had been made by the Commission at last month's meeting. The changes included the addition of the dimensions of the silt fences. The Commission had also requested the timing of construction. B. Knight said they will begin clearing the property this winter then will begin a step-by-step process with planning of construction and obtaining approvals.

M. McDonnell MOVED to approve the proposed activity as presented in the plan of record which covers the construction sequence and ENS controls. D. DeNunzio SECONDED the motion. MOTION CARRIED UNANIMOUSLY 4:0:0.

4. New Business

None.

6. Wetlands Agent Report

A. Barroso reported she closed out a lot of permits this month and reviewed the monthly report that was provided to the Commission. A. Barroso reported she visited 1 Notch Road, and everything looks great. A. Barroso stated the work at Shoddy Mill has made some progress and she will continue to monitor the activity. A. Barroso reported the Inland Wetlands brochures have been distributed and the Commission thanked her for doing an excellent job on them. R. Lally stated the CACIWC invitations have been received, and he will send it to the Commission. The annual meeting will be November 15, 2025.

7. Other

7a. Cease and Correct – Alexey Ouzonov & Tenant – 37 Notch Road – Debris in Wetlands

A. Barroso reported there has been no response from Mr. Ouzonov to date. R. Lally stated he sent a letter requesting the report of the soil testing. A. Barroso will follow up with Mr. Ouzonov.

7b. Ongoing Discussion & Review of Proposed Updates to Wetlands Regulation R. Lally reported he and A. Barroso gave a presentation on the Fee Schedule to the Selectmen this month. The proposal has been submitted to a subcommittee for

consideration. A. Barroso will send a note to Kathy McCavanagh for placement on the Selectmen's agenda.

8. Adjournment: J. Loersch MOVED to adjourn the meeting at 8:18 p.m. D. DeNunzio SECONDED the motion. MOTION CARRIED UNANIMOUSLY 4:0:0.

Respectfully submitted by Mary J. Johnston Mary J. Johnston

Please see the Minutes of subsequent meetings for corrections to these Minutes and any corrections hereto.



October 23, 2025

IW-25-16

Inland Wetlands

Status: Active

Submitted On: 10/23/2025

Primary Location

29 HEBRON RD BOLTON, CT 06043

Owner

No owner information

Applicant

Joseph Dillon

3 860-526-9591

bolton@nlja.com86 Main Street, P.O. Box

337

Chester, CT 06412

Internal Use	
≙ Conditions	
□ Petition Received?	△ Date Received
_	_
_	
■ Bond Required?	
_	

Additional Applicant Info Applicant Type* Other

Permit Info

Type of Application*	Permit For

New Application Application by Town of Bolton or Non-

profit group

Occupancy Type* Lots

Town of Bolton –

Work Description* ②

Construction of a soccer field at Herrick Park

Development Title

Herrick Memorial Park Soccer Field

△ Comments

Distance from Inland Wetlands and Watercourses:

Current Distance Proposed Distance
155 10

Wetland / Watercourses Project Information

Size of Subject Property (acres) 73	Total area of wetlands to be affected by the activity (acres)
	0
Open water body altered (acres) 0	Stream alternation (linear feet) 0
Buffer/upland area altered (acres) 1.15	Area of wetlands/watercourses restored, enhanced, or created (acres)

Described how the proposed activity affects wetlands, watercourses, and the regulated areas.

Described measures that will be taken to minimize the impact on wetlands, watercourses, and the regulated areas.

Sedimentation control fence, erosion control blankets and a construction entrance.

Is there a Conservation or Preservation Restruction on the Property?

Is this an activity associated with a use for which you intend to apply to the Planning & Zoning Commission?

No No

Please read and check the following statements. By checking these boxes, you agree to abide by the statutes and ordinances of the Town of Bolton and the State of Connecticut.

I understand that the Commission may require additional information at any time during the review of the application as described in Section 7.6 of the Inland Wetlands and Watercourses Regulations.*



The Applicant must ensure that this application is complete and conforms with the Inland Wetlands and Watercourses Regulations (available at the Land Use Office for \$10.00). Ten (10) copies of supporting documents must be provided. The Commission encourages the applicant to discuss any project with the Town Staff and/or the Commission before submitting an application. The Commission requests that applications be submitted at least one week before the meeting.*



The Agency shall monitor all Bolton wetland and watercourses and have enforcement powers as described in Section 14 of the Inland Wetlands and Watercourses Regulations. The Commission Members and designed agent(s) may make regular inspections upon reasonable notice of all regulated activities to investigate possible violations of the Inland Wetlands and Watercourses Regulations.*

If this application is filed with the Inland Wetlands
Agent under Section 12.1 of the Inland Wetlands and
Watercourses Regulations, the Applicant may appeal
the Agent's decision according to the process
descibed in section 12.2 of the Inland Wetlands and
Watercourses Regulations.*





Attorney Info

Name Address

City State

Zip Phone

Email

Engineer Information

Company Name Engineer Name Nathan L. Jacobson & Assoc. Joe Dillon **Address** City 86 Main St. Chester Zip State CT 06412-0337 Phone Registration # 860-526-9591 PEN 0022903 **Insurance Expiration AOR Email** jdillon@nlja.com Additional Project Info ■ Date of Receipt **△** Hearings Commencement Deadline

	□ Decision Deadline
-	-
Total Acreage	Distance to Town Line
73.92	
⊕ Extended	
Attachments	
Attachments	
Key Map of Property	
_ags_9873431e823d4f97b866c3909778	
Uploaded by Joseph Dillon on Oct 23, 2	025 at 10:57 AM
2025-10-22 Herrick Park.pdf	
2025-10-22 Herrick Park.pdf	
Uploaded by Joseph Dillon on Oct 23, 2	025 at 9:41 AM
Abutting Properties.pdf	

Uploaded by Danielle Palazzini on Oct 23, 2025 at 11:52 AM

Abutting Properties.pdf

ArcGIS Web Map Bolton Cent Bolton Herrick Memorial Park Town Owned Herrick Park Loumis Rd Legend **CRCOG Towns** Mask Parcel Polygons CAPITOL REGION COUNCIL OF GOVERNMENTS

Working together for a better region. Scale CRCOG makes no claims and no warranties, expressed or implied, concerning the 1:10,000 validity or accuracy of the GIS data presented on this map.

Created: 10/23/2025

Bit. BITUMINOUS Conc. CONCRETE CL&P CONNECTICUT LIGHT AND POWER EL. ELEVATION INV. INVERT N/F NOW OR FORMERLY RCP REINFORCED CONCRETE PIPE HDPE HIGH DENSITY POLYETHYLENE PIPE SNET SOUTHERN NEW ENGLAND TELEPHONE CO. T.O.W. TOP OF WALL TYP. TYPICAL

	LEGEND	
<u>Existing</u>		PROPOSED
100	INDEX CONTOUR	100
98	INTERMEDIATE CONTOUR	98
000000000000000000000000000000000000000	STONEWALL	
	APPROXIMATE WETLANDS	
	100' WETLANDS BOUNDARY	
	PROPERTY LINE	
0	IRON ROD	
A	SURVEY CONTROL	
D	UTILITY POLE	
	EDGE OF GRAVEL	
	EDGE OF PAVEMENT	
	DRAINAGE PIPE	
~~~~~~	TREE LINE	
	RIPRAP	的工作的
	GRAVEL	HODENIC
	EROSION CONTROL BLANKET	图的各种系统
	SEDIMENTATION FENCE	

### TOWN OF BOLTON




CONNECTICUT


## HERRICK MEMORIAL PARK SOCCER FIELD

### BOARD OF SELECTMEN

RODNEY FOURNIER, FIRST SELECTMAN
PAMELA SAWYER, SELECTMAN
TIMOTHY SADLER, SELECTMAN
ROBER MORRA, SELECTMAN
MATHER CLARK, SELECTMAN
AMANDA GORDON, SELECTMAN
GWEN MARRION, SELECTMAN


PERMITTING OCTOBER 2025









PH M. DILLON, P.E. GISTRATION No. 22903







I:\Civil 3D\09630011_Production Drawings\Permitting\09630011SP.dwg, 10/22/2025 10:31:56 AM, AutoCAD

ı	
	PROJECT NARRAT
	THE SUBJECT PROJECT INCLUDES TO DRAINAGE.
	ADDRESS OF PROPOSED USE: HERRICK MEMORIAL PARK
	29 HEBRON ROAD BOLTON, CT 06043
	ADDRESS OF OWNER'S AGENT:  JAMES RUPERT
	TOWN ADMINISTRATOR 222 BOLTON CENTER ROAD BOLTON, CT 06043
Ε	ADDRESS OF PROPERTY OWNER:
	TOWN OF BOLTON 222 BOLTON CENTER ROAD BOLTON, CT 06043
	CONSTRUCTION S
	IT IS PROPOSED TO PERFORM CONS SITE STABILIZATION MAY BE AS FOLL
ı	1. INSTALL CONSTRUCTION ENTR
l	<ol> <li>INSTALL SEDIMENT AND EROSI</li> <li>CLEAR VEGETATION, CUT TREE</li> </ol>
1	4. CONDUCT EARTHWORK CUTS A
4	<ul><li>5. INSTALL DRAINAGE STRUCTUR</li><li>6. INSTALL GRAVELS FOR ACCES:</li></ul>
	7. PLACE TOPSOIL AND SEED IN A
	<ol> <li>PLACE EROSION CONTROL BLA</li> <li>INSTALL FENCING AND GUIDE F</li> </ol>
	10. CLEAN UP AND REMOVE ALL CO SITE.
	11. SILT FENCE TO BE REMOVED V
	THE CONTRACTOR SELECTED TO CO EROSION CONTROL MEASURES ON T BOLTON CONSERVATION COMMISSION
	AND ZONING ENFORCEMENT OFFICE SHOULD ANY PROBLEMS OCCUR, TH
	CONTINGENCY PLAN
D	A MINIMUM OF TWO WEEKS PRIOR TO AND THE TOWN ENGINEER WITH THE THE EVENT OF AN EROSION AND/OR
	THE CONTRACTOR SHALL AT ALL TIN THE PROJECT SITE TO CONTROL UN
	EROSION AND SEDIME
	THE CONTRACTOR SHALL BE RESPO
	THE MINIMUM STANDARDS FOR ALL CONNECTICUT GUIDELINES FOR SOI
	MEANS AND TECHNIQUES MAY BE AL
	GENERAL GUIDELI  5. NO CONSTRUCTION ACTIVITY S
	FLOODPLAINS, DESIGNATED UI REQUIRED APPROVALS AND/O
$\exists$	TEMPORARY EROSION AND SECUMENT (     ALL EROSION AND SECUMENT (
	ALL EROSION AND SEDIMENT (     DISTURBED AREAS HAVE BEEN
	<ol> <li>THE CONTRACTOR SHALL LIMI REASONABLE CARE TO PROTE FEASIBLE.</li> </ol>
	9. WHERE PRACTICABLE, THE CO EXPOSED SOIL TO AREAS ACT
	THE PERIOD OF EXPOSURE OF ACCOMPLISHED AS SOON AS I
	<ol> <li>ADEQUATE PROVISIONS SHALI DAMAGE.</li> </ol>
	<ul><li>11. ALL MATERIAL FROM CLEARIN</li><li>12. WATER FROM DEWATERING O</li></ul>
	SUCH WATER SHALL BE DISCH SYSTEM ONLY WHEN APPROVI
	SEWER SYSTEM.  13. THE STORAGE, WASHING, FUE AREAS ONLY, IN THE EVENT O
	ENERGY AND ENVIRONMENTAL AGENT.
	PRESERVE AND CO
	MATERIALS
	SITE INVESTIGATIONS SHALL E ON THE SITE TO JUSTIFY STRIE
	SANDY CLAY LOAM, CLAY LOAI TESTING. IT SHALL BE FREE O BEING ABLE TO SUPPORT HEA
	GROWTH.  ALL TOPSOIL SHALL BE TESTE
$\dashv$	AND FERTILIZER.  INSTALLATION REQUIR
	STRIPPING OF TOPSOIL SHALL     DEPENDING ON THE SITE CON
	OPERATIONS.
	TOPSOIL SHALL BE STOCKPILE OFF-SITE SEDIMENT DAMAGE S     SIDE SLOPES OF STOCKPILES
	<ol> <li>SIDE SLOPES OF STOCKPILES</li> <li>A SEDIMENT BARRIER SHALL S</li> </ol>
	5. TEMPORARY SEEDING OF STO ACCORDANCE WITH THE TEMP
	PREVIOUSLY ESTABLISHED GF DRAWINGS.
в	7. WHERE THE PH OF THE SUBSO WITH THE SOIL TEST TO A PH 0
1	AFTER THE AREAS TO BE TOPS     TOPSOIL, THE SUBGRADE SHA
	INCHES TO ENSURE BONDING  9. TOPSOIL SHALL NOT BE PLACE
	9. TOPSOIL SHALL NOT BE PLACE IN A CONDITION THAT MAY OTH TOPSOIL SHALL BE UNIFORMLY ANY IRREGULARITIES IN THE S
	ANY IRREGULARITIES IN THE S ORDER TO PREVENT THE FORI  10. TOPSOIL SHALL BE COMPACTE
	10. TOPSOIL SHALL BE COMPACTE UNIFORM FIRM SEEDBED FOR INCREASES RUNOFF VELOCITY
	11. IMMEDIATELY FOLLOWING TOF AND/OR MULCHING.
	LAND GRADING
4	ALL GRADED OR DISTURBED A     ACCORDANCE WITH THE APPR
	2. AREAS TO BE FILLED SHALL BE OTHER OBJECTIONABLE MATE
	ALL FILLS SHALL BE COMPACT RELATED PROBLEMS.
	4. FILL MATERIAL SHALL BE FREE MATERIALS.
	5. FROZEN MATERIAL OR SOFT, N
	<ol><li>FILL SHALL NOT BE PLACED ON</li></ol>
	7. TOPSOILING SHALL BE ACCOM
	<ol> <li>TOPSOILING SHALL BE ACCOM</li> <li>ALL GRADED AREAS SHALL BE</li> </ol> DUST CONTROL

	PROJECT NARRATIVE:  THE SUBJECT PROJECT INCLUDES THE CONSTRUBENIAGE.  ADDRESS OF PROPOSED USE:
	HERRICK MEMORIAL PARK 29 HEBRON ROAD BOLTON, CT 06043 ADDRESS OF OWNER'S AGENT: JAMES RUPERT
E	TOWN ADMINISTRATOR 222 BOLTON CENTER ROAD BOLTON, CT 06043  ADDRESS OF PROPERTY OWNER: TOWN OF BOLTON
	222 BOLTON CENTER ROAD BOLTON, CT 06043  CONSTRUCTION SCHEDU
	IT IS PROPOSED TO PERFORM CONSTRUCTION II SITE STABILIZATION MAY BE AS FOLLOWS:  1. INSTALL CONSTRUCTION ENTRANCE. AND STABLE SERVICES AND STABLE SERVICES.
	2. INSTALL SEDIMENT AND EROSION CONTRO 3. CLEAR VEGETATION, CUT TREES AND GRID 4. CONDUCT EARTHWORK CUTS AND FILLS. 5. INSTALL DRAINAGE STRUCTURES AND PIPE
_	6. INSTALL GRAVELS FOR ACCESS DRIVE AND 7. PLACE TOPSOIL AND SEED IN ALL AREAS C 8. PLACE EROSION CONTROL BLANKETS ON S
	9. INSTALL FENCING AND GUIDE RAILS.  10. CLEAN UP AND REMOVE ALL CONSTRUCTION SITE.  11. SILT FENCE TO BE REMOVED WITHIN 30 DA
	THE CONTRACTOR SELECTED TO CONSTRUCT T EROSION CONTROL MEASURES ON THIS SITE. PF BOLTON CONSERVATION COMMISSION ENFORCE AND ZONING ENFORCEMENT OFFICERS WITH TH SHOULD ANY PROBLEMS OCCUR, THEN THE OWI
D	CONTINGENCY PLAN  A MINIMUM OF TWO WEEKS PRIOR TO THE STAR AND THE TOWN ENGINEER WITH THE NAMES AND THE EVENT OF AN EROSION AND/OR SEDIMENT OF
	THE CONTRACTOR SHALL AT ALL TIMES KEEP SU THE PROJECT SITE TO CONTROL UNFORESEEN I CONTRACTOR SHALL PROMPTLY STABILIZE THE EROSION AND SEDIMENT CON
	THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROJECT.  THE MINIMUM STANDARDS FOR ALL EROSION AN CONNECTICUT GUIDELINES FOR SOIL EROSION AMEANS AND TECHNIQUES MAY BE ALLOWED WIT
	GENERAL GUIDELINES:  5. NO CONSTRUCTION ACTIVITY SHALL TAKE FLOODPLAINS, DESIGNATED UPLAND REVII REQUIRED APPROVALS AND/OR PERMITS.
	TEMPORARY EROSION AND SEDIMENT CON     ALL EROSION AND SEDIMENT CONTROLS S     DISTURBED AREAS HAVE BEEN STABILIZED      THE CONTRACTOR SHALL LIMIT THE DISTU
	PREASONABLE CARE TO PROTECT AND PRE FEASIBLE.  9. WHERE PRACTICABLE, THE CONTRACTOR EXPOSED SOIL TO AREAS ACTIVELY UNDER THE PERIOD OF EXPOSURE OF DISTURBED
	ACCOMPLISHED AS SOON AS IS PRACTICAL  10. ADEQUATE PROVISIONS SHALL BE TAKEN DAMAGE.  11. ALL MATERIAL FROM CLEARING AND GRUB
С	12. WATER FROM DEWATERING OPERATIONS SUCH WATER SHALL BE DISCHARGED TO A SYSTEM ONLY WHEN APPROVED. NO WATE SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MARKET STORAGE.
	AREAS ONLY. IN THE EVENT OF A CONTAMENERGY AND ENVIRONMENTAL PROTECTION AGENT.  PRESERVE AND CONSER
	TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO IT ON THE SITE TO JUSTIFY STRIPPING. HIGH
	SANDY CLAY LOAM, CLAY LOAM). OTHER S TESTING. IT SHALL BE FREE OF DEBRIS, TI BEING ABLE TO SUPPORT HEALTHY VEGET GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECO
	AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINE DEPENDING ON THE SITE CONDITIONS. ALL OPERATIONS.
	2. TOPSOIL SHALL BE STOCKPILED IN SUCH A OFF-SITE SEDIMENT DAMAGE SHALL RESU  3. SIDE SLOPES OF STOCKPILES SHALL NOT I
	4. A SEDIMENT BARRIER SHALL SURROUND A 5. TEMPORARY SEEDING OF STOCKPILES SH. ACCORDANCE WITH THE TEMPORARY VEG 6. PREVIOUSLY ESTABLISHED GRADES ON TH DRAWINGS.
В	7. WHERE THE pH OF THE SUBSOIL IS 6.0 OR WITH THE SOIL TEST TO A pH OF 6.0 TO 6.5  8. AFTER THE AREAS TO BE TOPSOILED HAVE TOPSOIL, THE SUBGRADE SHALL BE LOOSE INCHES TO ENSURE BONDING OF THE TOP.
	9. TOPSOIL SHALL NOT BE PLACED WHILE IN. IN A CONDITION THAT MAY OTHERWISE BE TOPSOIL SHALL BE UNIFORMLY DISTRIBUT ANY IRREGULARITIES IN THE SURFACE RES ORDER TO PREVENT THE FORMATION OF D
	TOPSOIL SHALL BE COMPACTED ENOUGH 'UNIFORM FIRM SEEDBED FOR THE ESTABL INCREASES RUNOFF VELOCITY AND VOLUM     IMMEDIATELY FOLLOWING TOPSOIL APPLICAND/OR MULCHING.
_	LAND GRADING  1. ALL GRADED OR DISTURBED AREAS INCLU ACCORDANCE WITH THE APPROVED SEDIM
	2. AREAS TO BE FILLED SHALL BE CLEARED, OTHER OBJECTIONABLE MATERIAL.  3. ALL FILLS SHALL BE COMPACTED AS REQUIRELATED PROBLEMS.
	4. FILL MATERIAL SHALL BE FREE OF BRUSH, MATERIALS.  5. FROZEN MATERIAL OR SOFT, MUCKY OR HI
	6. FILL SHALL NOT BE PLACED ON A FROZEN 7. TOPSOILING SHALL BE ACCOMPLISHED IN A 8. ALL GRADED AREAS SHALL BE PERMANEN

	PROJECT NARRATIVI
	THE SUBJECT PROJECT INCLUDES THE C
	DRAINAGE.  ADDRESS OF PROPOSED USE:
	HERRICK MEMORIAL PARK 29 HEBRON ROAD BOLTON, CT 06043
	ADDRESS OF OWNER'S AGENT:
	JAMES RUPERT TOWN ADMINISTRATOR 222 BOLTON CENTER ROAD
Εĺ	BOLTON, CT 06043  ADDRESS OF PROPERTY OWNER:
	TOWN OF BOLTON 222 BOLTON CENTER ROAD BOLTON, CT 06043
	CONSTRUCTION SCH
	IT IS PROPOSED TO PERFORM CONSTRU SITE STABILIZATION MAY BE AS FOLLOW:
	INSTALL CONSTRUCTION ENTRANC     INSTALL SEDIMENT AND EROSION (
	INSTALL SEDIMENT AND EROSION O     CLEAR VEGETATION, CUT TREES AI
	<ul><li>4. CONDUCT EARTHWORK CUTS AND</li><li>5. INSTALL DRAINAGE STRUCTURES A</li></ul>
$\dashv$	6. INSTALL GRAVELS FOR ACCESS DR
	<ul><li>7. PLACE TOPSOIL AND SEED IN ALL A</li><li>8. PLACE EROSION CONTROL BLANKE</li></ul>
	9. INSTALL FENCING AND GUIDE RAILS
	CLEAN UP AND REMOVE ALL CONS' SITE.
	11. SILT FENCE TO BE REMOVED WITH  THE CONTRACTOR SELECTED TO CONST  EROSION CONTROL MEASURES ON THIS
	EROSION CONTROL MEASURES ON THIS BOLTON CONSERVATION COMMISSION E AND ZONING ENFORCEMENT OFFICERS I SHOULD ANY PROBLEMS OCCUR, THEN I
	CONTINGENCY PLAN
D	A MINIMUM OF TWO WEEKS PRIOR TO TH AND THE TOWN ENGINEER WITH THE NAI THE EVENT OF AN EROSION AND/OR SED
	THE EVENT OF AN EROSION AND/OR SED  THE CONTRACTOR SHALL AT ALL TIMES I  THE PROJECT SITE TO CONTROL LINEOR
	THE PROJECT SITE TO CONTROL UNFOR CONTRACTOR SHALL PROMPTLY STABILI
	THE CONTRACTOR SHALL BE RESPONSIE
	PROJECT.  THE MINIMUM STANDARDS FOR ALL ERO CONNECTICUT GUIDELINES FOR SOIL FR
	CONNECTICUT GUIDELINES FOR SOIL ER MEANS AND TECHNIQUES MAY BE ALLOW
	GENERAL GUIDELINE  5. NO CONSTRUCTION ACTIVITY SHAL
_	FLOODPLAINS, DESIGNATED UPLAN REQUIRED APPROVALS AND/OR PE
	TEMPORARY EROSION AND SEDIME     ALL EROSION AND SEDIMENT CONT
	DISTURBED AREAS HAVE BEEN STA  8. THE CONTRACTOR SHALL LIMIT THIS PERSONARILE CARE TO PROTECT A
	REASONABLE CARE TO PROTECT A FEASIBLE.  9. WHERE PRACTICABLE, THE CONTR
	9. WHERE PRACTICABLE, THE CONTR EXPOSED SOIL TO AREAS ACTIVEL' THE PERIOD OF EXPOSURE OF DIS' ACCOMPLISHED AS SOON AS IS PR
	ADEQUATE PROVISIONS SHALL BE DAMAGE.
	11. ALL MATERIAL FROM CLEARING AN
	<ol> <li>WATER FROM DEWATERING OPERA SUCH WATER SHALL BE DISCHARG SYSTEM ONLY WHEN APPROVED. N SEWER SYSTEM.</li> </ol>
	13. THE STORAGE, WASHING, FUELING AREAS ONLY. IN THE EVENT OF A ENERGY AND ENVIRONMENTAL PRO
	PRESERVE AND CON
	TOPSOILING
	MATERIALS SITE INVESTIGATIONS SHALL BE MA
	ON THE SITE TO JUSTIFY STRIPPIN SANDY CLAY LOAM, CLAY LOAM). ( TESTING. IT SHALL BE FREE OF DE BEING ABLE TO SUPPORT HEALTH)
	GROWTH.  ALL TOPSOIL SHALL BE TESTED BY AND FERTILIZER.
	INSTALLATION REQUIREME  1. STRIPPING OF TOPSOIL SHALL BE OF
	DEPENDING ON THE SITE CONDITION OPERATIONS.
	TOPSOIL SHALL BE STOCKPILED IN OFF-SITE SEDIMENT DAMAGE SHALL
	<ol> <li>SIDE SLOPES OF STOCKPILES SHA</li> <li>A SEDIMENT BARRIER SHALL SURF</li> </ol>
	5. TEMPORARY SEEDING OF STOCKP ACCORDANCE WITH THE TEMPORA
	PREVIOUSLY ESTABLISHED GRADE DRAWINGS.
в	7. WHERE THE pH OF THE SUBSOIL IS WITH THE SOIL TEST TO A pH OF 6.
	8. AFTER THE AREAS TO BE TOPSOILI TOPSOIL, THE SUBGRADE SHALL BI INCHES TO ENSURE BONDING OF T
	9. TOPSOIL SHALL NOT BE PLACED W IN A CONDITION THAT MAY OTHERV
	TOPSOIL SHALL BE UNIFORMLY DIS ANY IRREGULARITIES IN THE SURF ORDER TO PREVENT THE FORMATI
	TOPSOIL SHALL BE COMPACTED EN UNIFORM FIRM SEEDBED FOR THE INCREASES RUNOFF VELOCITY AND
	IMMEDIATELY FOLLOWING TOPSOIL AND/OR MULCHING.
	LAND GRADING
4	ALL GRADED OR DISTURBED AREA     ACCORDANCE WITH THE APPROVE  APPROXIMATE OF SULED SUAL DESCRIPTION
	AREAS TO BE FILLED SHALL BE CLE OTHER OBJECTIONABLE MATERIAL  ALL FILLS SHALL BE COMPACTED A
	ALL FILLS SHALL BE COMPACTED A RELATED PROBLEMS.      FILL MATERIAL SHALL BE FREE OF
	MATERIALS.
•	<ol><li>FROZEN MATERIAL OR SOFT, MUCH</li></ol>

十	
	PROJECT NARRATION THE SUBJECT PROJECT INCLUDES THE
	DRAINAGE.  ADDRESS OF PROPOSED USE:
	HERRICK MEMORIAL PARK 29 HEBRON ROAD BOLTON, CT 06043
	ADDRESS OF OWNER'S AGENT:
	JAMES RUPERT TOWN ADMINISTRATOR 222 BOLTON CENTER ROAD BOLTON, CT 06043
E	ADDRESS OF PROPERTY OWNER:
	TOWN OF BOLTON 222 BOLTON CENTER ROAD BOLTON, CT 06043
	CONSTRUCTION SO
	IT IS PROPOSED TO PERFORM CONST SITE STABILIZATION MAY BE AS FOLLO
	<ol> <li>INSTALL CONSTRUCTION ENTRA</li> <li>INSTALL SEDIMENT AND EROSIO</li> </ol>
	CLEAR VEGETATION, CUT TREES     CONDUCT EARTHWORK CUTS AI
	INSTALL DRAINAGE STRUCTURE
┪	<ul><li>6. INSTALL GRAVELS FOR ACCESS</li><li>7. PLACE TOPSOIL AND SEED IN AL</li></ul>
	8. PLACE EROSION CONTROL BLAN
	INSTALL FENCING AND GUIDE RA      CLEAN UP AND REMOVE ALL COI     SITE.
	11. SILT FENCE TO BE REMOVED WI
	THE CONTRACTOR SELECTED TO CON EROSION CONTROL MEASURES ON TH BOLTON CONSERVATION COMMISSION
	AND ZONING ENFORCEMENT OFFICER SHOULD ANY PROBLEMS OCCUR, THE CONTINGENCY PLAN
D	A MINIMUM OF TWO WEEKS PRIOR TO AND THE TOWN ENGINEER WITH THE THE EVENT OF AN EROSION AND/OR S
	THE CONTRACTOR SHALL AT ALL TIME THE PROJECT SITE TO CONTROL UNFO CONTRACTOR SHALL PROMPTLY STAE
	EROSION AND SEDIME
	THE CONTRACTOR SHALL BE RESPON PROJECT.
	THE MINIMUM STANDARDS FOR ALL EI CONNECTICUT GUIDELINES FOR SOIL MEANS AND TECHNIQUES MAY BE ALL
	GENERAL GUIDELIN
	<ol> <li>NO CONSTRUCTION ACTIVITY SE FLOODPLAINS, DESIGNATED UPI REQUIRED APPROVALS AND/OR</li> </ol>
$\dashv$	6. TEMPORARY EROSION AND SED
	ALL EROSION AND SEDIMENT CO DISTURBED AREAS HAVE BEEN S     THE CONTRACTOR SHALL LIMIT
	8. THE CONTRACTOR SHALL LIMIT REASONABLE CARE TO PROTEC FEASIBLE.
	9. WHERE PRACTICABLE, THE CON EXPOSED SOIL TO AREAS ACTIV THE PERIOD OF EXPOSURE OF E ACCOMBUSINED AS SOON AS IS
	ACCOMPLISHED AS SOON AS IS  10. ADEQUATE PROVISIONS SHALL I DAMAGE.
	11. ALL MATERIAL FROM CLEARING
c	12. WATER FROM DEWATERING OPE SUCH WATER SHALL BE DISCHA SYSTEM ONLY WHEN APPROVED
	SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELI AREAS ONLY. IN THE EVENT OF
	ENERGY AND ENVIRONMENTAL I AGENT.
	PRESERVE AND CC TOPSOILING
	MATERIALS
	SITE INVESTIGATIONS SHALL BE ON THE SITE TO JUSTIFY STRIPF SANDY CLAY LOAM, CLAY LOAM)
	TESTING. IT SHALL BE FREE OF BEING ABLE TO SUPPORT HEALT GROWTH.
$\dashv$	ALL TOPSOIL SHALL BE TESTED AND FERTILIZER.
	INSTALLATION REQUIRE  1. STRIPPING OF TOPSOIL SHALL B
	DEPENDING ON THE SITE CONDI OPERATIONS.
	TOPSOIL SHALL BE STOCKPILED OFF-SITE SEDIMENT DAMAGE SHALL SH
	<ol> <li>SIDE SLOPES OF STOCKPILES SI</li> <li>A SEDIMENT BARRIER SHALL SU</li> </ol>
	5. TEMPORARY SEEDING OF STOC ACCORDANCE WITH THE TEMPO
	PREVIOUSLY ESTABLISHED GRAD DRAWINGS.
в	7. WHERE THE pH OF THE SUBSOIL WITH THE SOIL TEST TO A pH OF
	<ol> <li>AFTER THE AREAS TO BE TOPSO TOPSOIL, THE SUBGRADE SHALL INCHES TO ENSURE BONDING O</li> </ol>
	TOPSOIL SHALL NOT BE PLACED IN A CONDITION THAT MAY OTHE TOPSOIL SHALL BE UNIFORMLY
	ANY IRREGULARITIES IN THE SU ORDER TO PREVENT THE FORM.  10. TOPSOIL SHALL BE COMPACTED
	UNIFORM FIRM SEEDBED FOR TH INCREASES RUNOFF VELOCITY A
	11. IMMEDIATELY FOLLOWING TOPS AND/OR MULCHING.
	LAND GRADING  1. ALL GRADED OR DISTURBED AR
$\dashv$	ACCORDANCE WITH THE APPRO  2. AREAS TO BE FILLED SHALL BE (
ı	OTHER OBJECTIONABLE MATER  3. ALL FILLS SHALL BE COMPACTED RELATED PROBLEMS.
	RELATED PROBLEMS.
	<ol> <li>FILL MATERIAL SHALL BE FREE OF MATERIALS.</li> </ol>
	MATERIALS. 5. FROZEN MATERIAL OR SOFT, ML
	MATERIALS.
	MATERIALS.  5. FROZEN MATERIAL OR SOFT, ML  6. FILL SHALL NOT BE PLACED ON A  7. TOPSOILING SHALL BE ACCOMP  8. ALL GRADED AREAS SHALL BE P
	MATERIALS.  5. FROZEN MATERIAL OR SOFT, ML  6. FILL SHALL NOT BE PLACED ON 7  7. TOPSOILING SHALL BE ACCOMP
A	MATERIALS.  5. FROZEN MATERIAL OR SOFT, MI  6. FILL SHALL NOT BE PLACED ON  7. TOPSOILING SHALL BE ACCOMP  8. ALL GRADED AREAS SHALL BE F  DUST CONTROL

	1
	PROJECT NARRATIVE:
	THE SUBJECT PROJECT INCLUDES THE CONSTRUCTION OF A GRASSED SOCCER FIELD WITH ASSOCIATED PARKING AREAS AND DRAINAGE.
	ADDRESS OF PROPOSED USE:  HERRICK MEMORIAL PARK 29 HEBRON ROAD
	BOLTON, CT 06043  ADDRESS OF OWNER'S AGENT:
	JAMES RUPERT TOWN ADMINISTRATOR 222 BOLTON CENTER ROAD
E	BOLTON, CT 06043  ADDRESS OF PROPERTY OWNER:
	TOWN OF BOLTON 222 BOLTON CENTER ROAD BOLTON, CT 06043
	CONSTRUCTION SCHEDULING:
	IT IS PROPOSED TO PERFORM CONSTRUCTION IN THE SUMMER OF 2015. IN GENERAL, THE SEQUENCE FOR CONSTRUCTION AND SITE STABILIZATION MAY BE AS FOLLOWS:
	<ol> <li>INSTALL CONSTRUCTION ENTRANCE. AND SEDIMENT AND EROSION CONTROLS.</li> <li>INSTALL SEDIMENT AND EROSION CONTROLS.</li> </ol>
	<ol> <li>CLEAR VEGETATION, CUT TREES AND GRID STUMPS WITHIN THE CLEARING LIMITS.</li> <li>CONDUCT EARTHWORK CUTS AND FILLS.</li> </ol>
	<ul><li>5. INSTALL DRAINAGE STRUCTURES AND PIPE.</li><li>6. INSTALL GRAVELS FOR ACCESS DRIVE AND PARKING AREA.</li></ul>
	7. PLACE TOPSOIL AND SEED IN ALL AREAS OTHER THAN AREAS SURFACED WITH GRAVEL.
	8. PLACE EROSION CONTROL BLANKETS ON SLOPES AS SPECIFIED ON DRAWINGS.  9. INSTALL FENCING AND GUIDE RAILS.
	10. CLEAN UP AND REMOVE ALL CONSTRUCTION MATERIALS, EQUIPMENT, SURPLUS MATERIALS AND DEBRIS FROM PROJECT SITE.
	11. SILT FENCE TO BE REMOVED WITHIN 30 DAYS AFTER STABILIZATION OF DISTURBED AREAS.  THE CONTRACTOR SELECTED TO CONSTRUCT THIS PROJECT WILL BE RESPONSIBLE FOR IMPLEMENTATION OF SEDIMENT AND EROSION CONTROL MEASURES ON THIS SITE. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR WILL PROVIDE THE
	BOLTON CONSERVATION COMMISSION ENFORCEMENT OFFICERS, INLAND WETLANDS ENFORCEMENT OFFICERS, TOWN ENGINEER: AND ZONING ENFORCEMENT OFFICERS WITH THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE RESPONSIBLE PERSON. SHOULD ANY PROBLEMS OCCUR, THEN THE OWNER'S AGENT SHOULD BE CONTACTED.
D	CONTINGENCY PLAN  A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE THE OWNER'S AGENT AND THE TOWN ENGINEER WITH THE NAMES AND TELEPHONE NUMBERS OF THE RESPONSIBLE PERSONS TO BE CONTACTED IN
	THE EVENT OF AN EROSION AND/OR SEDIMENT CONTROL PROBLEM.  THE CONTRACTOR SHALL AT ALL TIMES KEEP SUFFICIENT ADDITIONAL SEDIMENTATION CONTROL FENCE AND/OR HAY BALES ON
	THE PROJECT SITE TO CONTROL UNFORESEEN EROSION AND/OR SEDIMENT PROBLEMS. IN THE EVENT OF A PROBLEM THE CONTRACTOR SHALL PROMPTLY STABILIZE THE PROBLEM AND CONTAIN ANY SEDIMENT AND THEN NOTIFY THE OWNER'S AGENT.  EROSION AND SEDIMENT CONTROL
	THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF THE EROSION AND SEDIMENT CONTROL PLAN FOR THE PROJECT.
	THE MINIMUM STANDARDS FOR ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE THOSE OUTLINED IN THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL", LATEST REVISION. ALTERNATIVE MEASURES, METHODS
l	MEANS AND TECHNIQUES MAY BE ALLOWED WITH THE PRIOR APPROVAL OF THE OWNER'S AGENT.  GENERAL GUIDELINES:
	<ol> <li>NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE WITHIN AREAS DESIGNATED AS INLAND WETLANDS, WATERCOURSES OR FLOODPLAINS, DESIGNATED UPLAND REVIEW ZONES OR WITHIN STREAM CHANNEL ENCROACHMENT LINES WITHOUT ALL REQUIRED APPROVALS AND/OR PERMITS.</li> </ol>
┪	6. TEMPORARY EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION.
	<ol> <li>ALL EROSION AND SEDIMENT CONTROLS SHALL BE MAINTAINED CONTINUOUSLY AND SHALL NOT BE REMOVED UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED.</li> <li>THE CONTRACTOR SHALL LIMIT THE DISTURBANCE OF LAND TO THOSE AREAS SHOWN ON THE DRAWINGS AND SHALL TAKE REASONABLE CARE TO PROTECT AND PRESERVE EXISTING VEGETATION WITHIN THE LIMITS OF DISTURBANCE WHERE</li> </ol>
	FEASIBLE.  9. WHERE PRACTICABLE, THE CONTRACTOR SHALL PLAN HIS CONSTRUCTION OPERATIONS SO AS TO LIMIT THE AREAS OF EXPOSED SOIL TO AREAS ACTIVELY UNDER CONSTRUCTION. THE CONTRACTOR SHALL TAKE REASONABLE CARE TO LIMIT TO A
	THE PERIOD OF EXPOSURE OF DISTURBED AREAS. THE INSTALLATION OF PERMANENT VEGETATIVE MEASURES SHALL BE ACCOMPLISHED AS SOON AS IS PRACTICABLE.  10. ADEQUATE PROVISIONS SHALL BE TAKEN TO PROTECT ALL EXPOSED CUT AND FILL SLOPES FROM SURFACE WATER FLOW
	DAMAGE.  11. ALL MATERIAL FROM CLEARING AND GRUBBING OPERATIONS SHALL BE DISPOSED OF IN A LAWFUL MANNER.
c	12. WATER FROM DEWATERING OPERATIONS SHALL NOT BE DISCHARGED DIRECTLY TO ANY WETLAND OR WATERCOURSE. SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.
	13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER'S
	PRESERVE AND CONSERVE SOIL
	TOPSOILING  MATERIALS
	SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOAM SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE O
	BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLANT GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME
$\dashv$	AND FERTILIZER.  INSTALLATION REQUIREMENTS
	<ol> <li>STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VARY DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.</li> </ol>
	TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.
	<ol> <li>SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.</li> <li>A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.</li> </ol>
	5. TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPLETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.
	PREVIOUSLY ESTABLISHED GRADES ON THE AREAS TO BE TOPSOILED SHALL BE MAINTAINED ACCORDING TO THE DRAWINGS.  WHERE THE SHARE HERE SHOULD SHARE SHOULD ACCORDING ACC
в	<ol> <li>WHERE THE pH OF THE SUBSOIL IS 6.0 OR LESS, GROUND AGRICULTURAL LIMESTONE SHALL BE SPREAD IN ACCORDANCE WITH THE SOIL TEST TO A pH OF 6.0 TO 6.5 OR THE VEGETATIVE ESTABLISHMENT PRACTICE BEING USED.</li> <li>AFTER THE AREAS TO BE TOPSOILED HAVE BEEN BROUGHT TO GRADE, AND IMMEDIATELY PRIOR TO SPREADING THE TOPSOIL, THE SUBGRADE SHALL BE LOOSENED BY DISCING OR SCARIFYING OR TRACKING TO A DEPTH OF AT LEAST 4</li> </ol>
	INCHES TO ENSURE BONDING OF THE TOPSOIL AND SUBSOIL.  9. TOPSOIL SHALL NOT BE PLACED WHILE IN A FROZEN OR MUDDY CONDITION, WHEN THE SUBGRADE IS EXCESSIVELY WET, OF IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING OR PROPOSED SODDING OR SEEDING. THE
	TOPSOIL SHALL BE UNIFORMLY DISTRIBUTED TO A MINIMUM COMPACTED DEPTH OF 6 INCHES, UNLESS OTHERWISE NOTED. ANY IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOILING OR OTHER OPERATIONS SHALL BE CORRECTED IN ORDER TO PREVENT THE FORMATION OF DEPRESSIONS OR WATER POCKETS.
	10. TOPSOIL SHALL BE COMPACTED ENOUGH TO ENSURE GOOD CONTACT WITH THE UNDERLYING SOIL AND TO OBTAIN A UNIFORM FIRM SEEDBED FOR THE ESTABLISHMENT OF A DURABLE TURF. UNDUE COMPACTION IS TO BE AVOIDED AS IT INCREASES RUNOFF VELOCITY AND VOLUME, AND PREVENTS SEED GERMINATION.
	11. IMMEDIATELY FOLLOWING TOPSOIL APPLICATION, PROTECT THE TOPSOIL FROM EROSION BY EITHER SODDING, SEEDING AND/OR MULCHING.
	LAND GRADING  1. ALL GRADED OR DISTURBED AREAS INCLUDING SLOPES SHALL BE PROTECTED DURING CLEARING AND CONSTRUCTION IN
1	ACCORDANCE WITH THE APPROVED SEDIMENT CONTROL PLAN UNTIL THEY ARE PERMANENTLY STABILIZED.  2. AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS OF OTHER OBJECTIONABLE MATERIAL.
	OTHER OBJECTIONABLE MATERIAL.  3. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS.
	FILL MATERIAL SHALL BE FREE OF BRUSH, RUBBISH, ROCKS, LOGS, STUMPS, BUILDING DEBRIS AND OTHER OBJECTIONABLE MATERIALS.
	<ul><li>5. FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS.</li><li>6. FILL SHALL NOT BE PLACED ON A FROZEN FOUNDATION.</li></ul>
	7. TOPSOILING SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE REQUIREMENTS FOR TOPSOILING.  8. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY FOLLOWING FINISHED GRADING.
	8. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY FOLLOWING FINISHED GRADING.  DUST CONTROL
A	INSTALLATION REQUIREMENTS  WATER
	THE EXPOSED SOIL SURFACE SHALL BE MOISTENED PERIODICALLY WITH ADEQUATE QUANTITIES OF WATER TO CONTROL DUST.
1	STONE

PROJECT NARRATIVE:  THE SUBJECT PROJECT INCLUDES THE CONSTRUCTION OF A GRASSED SOCCER FIELD WITH ASSOCIATED PARKING AREAS AND DRAINAGE.
ADDRESS OF PROPOSED USE: HERRICK MEMORIAL PARK
29 HEBRON ROAD BOLTON, CT 06043
ADDRESS OF OWNER'S AGENT:  JAMES RUPERT TOWN ADMINISTRATOR
222 BOLTON CENTER ROAD BOLTON, CT 06043  ADDRESS OF PROPERTY OWNER:
TOWN OF BOLTON 222 BOLTON CENTER ROAD BOLTON, CT 06043
CONSTRUCTION SCHEDULING:
IT IS PROPOSED TO PERFORM CONSTRUCTION IN THE SUMMER OF 2015. IN GENERAL, THE SEQUENCE FOR CONSTRUCTION AND SITE STABILIZATION MAY BE AS FOLLOWS:
INSTALL CONSTRUCTION ENTRANCE. AND SEDIMENT AND EROSION CONTROLS.     INSTALL SEDIMENT AND EROSION CONTROLS.
<ol> <li>CLEAR VEGETATION, CUT TREES AND GRID STUMPS WITHIN THE CLEARING LIMITS.</li> <li>CONDUCT EARTHWORK CUTS AND FILLS.</li> </ol>
<ul><li>5. INSTALL DRAINAGE STRUCTURES AND PIPE.</li><li>6. INSTALL GRAVELS FOR ACCESS DRIVE AND PARKING AREA.</li></ul>
<ol> <li>PLACE TOPSOIL AND SEED IN ALL AREAS OTHER THAN AREAS SURFACED WITH GRAVEL.</li> <li>PLACE EROSION CONTROL BLANKETS ON SLOPES AS SPECIFIED ON DRAWINGS.</li> </ol>
<ol> <li>INSTALL FENCING AND GUIDE RAILS.</li> <li>CLEAN UP AND REMOVE ALL CONSTRUCTION MATERIALS, EQUIPMENT, SURPLUS MATERIALS AND DEBRIS FROM PROJECT</li> </ol>
SITE.  11. SILT FENCE TO BE REMOVED WITHIN 30 DAYS AFTER STABILIZATION OF DISTURBED AREAS.
THE CONTRACTOR SELECTED TO CONSTRUCT THIS PROJECT WILL BE RESPONSIBLE FOR IMPLEMENTATION OF SEDIMENT AND EROSION CONTROL MEASURES ON THIS SITE. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR WILL PROVIDE THE BOLTON CONSERVATION COMMISSION ENFORCEMENT OFFICERS, INLAND WETLANDS ENFORCEMENT OFFICERS, TOWN ENGINEERS AND ZONING ENFORCEMENT OFFICERS WITH THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE RESPONSIBLE PERSON. SHOULD ANY PROBLEMS OCCUR, THEN THE OWNER'S AGENT SHOULD BE CONTACTED.  CONTINGENCY PLAN
A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE THE OWNER'S AGENT AND THE TOWN ENGINEER WITH THE NAMES AND TELEPHONE NUMBERS OF THE RESPONSIBLE PERSONS TO BE CONTACTED IN THE EVENT OF AN EROSION AND/OR SEDIMENT CONTROL PROBLEM.
THE CONTRACTOR SHALL AT ALL TIMES KEEP SUFFICIENT ADDITIONAL SEDIMENTATION CONTROL FENCE AND/OR HAY BALES ON THE PROJECT SITE TO CONTROL UNFORESEEN EROSION AND/OR SEDIMENT PROBLEMS. IN THE EVENT OF A PROBLEM THE CONTRACTOR SHALL PROMPTLY STABILIZE THE PROBLEM AND CONTAIN ANY SEDIMENT AND THEN NOTIFY THE OWNER'S AGENT.  EROSION AND SEDIMENT CONTROL
THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF THE EROSION AND SEDIMENT CONTROL PLAN FOR THE PROJECT.  THE MINIMUM STANDARDS FOR ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE THOSE OUTLINED IN THE "2002 CONNECTICAL CONTROL OF THE PROJECT OF THE
CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL", LATEST REVISION. ALTERNATIVE MEASURES, METHODS MEANS AND TECHNIQUES MAY BE ALLOWED WITH THE PRIOR APPROVAL OF THE OWNER'S AGENT.  GENERAL GUIDELINES:
5. NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE WITHIN AREAS DESIGNATED AS INLAND WETLANDS, WATERCOURSES OR FLOODPLAINS, DESIGNATED UPLAND REVIEW ZONES OR WITHIN STREAM CHANNEL ENCROACHMENT LINES WITHOUT ALL
REQUIRED APPROVALS AND/OR PERMITS.  6. TEMPORARY EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION.
<ol> <li>ALL EROSION AND SEDIMENT CONTROLS SHALL BE MAINTAINED CONTINUOUSLY AND SHALL NOT BE REMOVED UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED.</li> <li>THE CONTRACTOR SHALL LIMIT THE DISTURBANCE OF LAND TO THOSE AREAS SHOWN ON THE DRAWINGS AND SHALL TAKE</li> </ol>
REASONABLE CARE TO PROTECT AND PRESERVE EXISTING VEGETATION WITHIN THE LIMITS OF DISTURBANCE WHERE FEASIBLE.
<ol> <li>WHERE PRACTICABLE, THE CONTRACTOR SHALL PLAN HIS CONSTRUCTION OPERATIONS SO AS TO LIMIT THE AREAS OF EXPOSED SOIL TO AREAS ACTIVELY UNDER CONSTRUCTION. THE CONTRACTOR SHALL TAKE REASONABLE CARE TO LIMIT THE PERIOD OF EXPOSURE OF DISTURBED AREAS. THE INSTALLATION OF PERMANENT VEGETATIVE MEASURES SHALL BE ACCOMPLISHED AS SOON AS IS PRACTICABLE.</li> <li>ADEQUATE PROVISIONS SHALL BE TAKEN TO PROTECT ALL EXPOSED CUT AND FILL SLOPES FROM SURFACE WATER FLOW</li> </ol>
DAMAGE.  11. ALL MATERIAL FROM CLEARING AND GRUBBING OPERATIONS SHALL BE DISPOSED OF IN A LAWFUL MANNER.
<ol> <li>WATER FROM DEWATERING OPERATIONS SHALL NOT BE DISCHARGED DIRECTLY TO ANY WETLAND OR WATERCOURSE.     SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE     SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY     SEWER SYSTEM.</li> <li>THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED</li> </ol>
AREAS ONLY. ÎN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER'S AGENT.
PRESERVE AND CONSERVE SOIL TOPSOILING
MATERIALS
SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOAM SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE OF BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLANT GROWTH.
ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS
<ol> <li>STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VARY DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.</li> </ol>
TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.
<ol> <li>SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.</li> <li>A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.</li> </ol>
5. TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPLETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.
PREVIOUSLY ESTABLISHED GRADES ON THE AREAS TO BE TOPSOILED SHALL BE MAINTAINED ACCORDING TO THE DRAWINGS.  WINTER THE HIGH THE CHESCHIE CHESCHIE AND ADDICATE THE CHESCHIE CHARLES TO BE TOPSOILED AND ADDICATE THE CHESCHIE CHARLES TO BE TOPSOILED AND ADDICATE THE CHARLES TO BE TO
<ol> <li>WHERE THE pH OF THE SUBSOIL IS 6.0 OR LESS, GROUND AGRICULTURAL LIMESTONE SHALL BE SPREAD IN ACCORDANCE WITH THE SOIL TEST TO A pH OF 6.0 TO 6.5 OR THE VEGETATIVE ESTABLISHMENT PRACTICE BEING USED.</li> <li>AFTER THE AREAS TO BE TOPSOILED HAVE BEEN BROUGHT TO GRADE, AND IMMEDIATELY PRIOR TO SPREADING THE</li> </ol>
TOPSOIL, THE SUBGRADE SHALL BE LOOSENED BY DISCING OR SCARIFYING OR TRACKING TO A DEPTH OF AT LEAST 4 INCHES TO ENSURE BONDING OF THE TOPSOIL AND SUBSOIL.  9. TOPSOIL SHALL NOT BE PLACED WHILE IN A FROZEN OR MUDDY CONDITION, WHEN THE SUBGRADE IS EXCESSIVELY WET, OF
IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING OR PROPOSED SODDING OR SEEDING. THE TOPSOIL SHALL BE UNIFORMLY DISTRIBUTED TO A MINIMUM COMPACTED DEPTH OF 6 INCHES, UNLESS OTHERWISE NOTED. ANY IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOILING OR OTHER OPERATIONS SHALL BE CORRECTED IN ORDER TO PREVENT THE FORMATION OF DEPRESSIONS OR WATER POCKETS.
10. TOPSOIL SHALL BE COMPACTED ENOUGH TO ENSURE GOOD CONTACT WITH THE UNDERLYING SOIL AND TO OBTAIN A UNIFORM FIRM SEEDBED FOR THE ESTABLISHMENT OF A DURABLE TURF. UNDUE COMPACTION IS TO BE AVOIDED AS IT INCREASES RUNOFF VELOCITY AND VOLUME, AND PREVENTS SEED GERMINATION.  11. IMMEDIATELY FOLLOWING TOPSOIL APPLICATION, PROTECT THE TOPSOIL FROM EROSION BY FITHER SONDING. SEEDING.
11. IMMEDIATELY FOLLOWING TOPSOIL APPLICATION, PROTECT THE TOPSOIL FROM EROSION BY EITHER SODDING, SEEDING AND/OR MULCHING.  LAND GRADING
ALL GRADED OR DISTURBED AREAS INCLUDING SLOPES SHALL BE PROTECTED DURING CLEARING AND CONSTRUCTION IN ACCORDANCE WITH THE APPROVED SEDIMENT CONTROL PLAN UNTIL THEY ARE PERMANENTLY STABILIZED.
AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS OF OTHER OBJECTIONABLE MATERIAL.
<ol> <li>ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS.</li> <li>FILL MATERIAL SHALL BE FREE OF BRUSH, RUBBISH, ROCKS, LOGS, STUMPS, BUILDING DEBRIS AND OTHER OBJECTIONABLE</li> </ol>
MATERIALS.
5. FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS.
<ol> <li>FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS.</li> <li>FILL SHALL NOT BE PLACED ON A FROZEN FOUNDATION.</li> <li>TOPSOILING SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE REQUIREMENTS FOR TOPSOILING.</li> </ol>
6. FILL SHALL NOT BE PLACED ON A FROZEN FOUNDATION.

	TOWN OF BOLTON
	222 BOLTON CENTER ROAD BOLTON, CT 06043
	CONSTRUCTION SCHEDULING:
	IT IS PROPOSED TO PERFORM CONSTRUCTION IN THE SUMMER OF 2015. IN GENERAL, THE SEQUENCE FOR CONSTRUCTION AND
	SITE STABILIZATION MAY BE AS FOLLOWS:  1. INSTALL CONSTRUCTION ENTRANCE. AND SEDIMENT AND EROSION CONTROLS.
	2. INSTALL SEDIMENT AND EROSION CONTROLS.
	3. CLEAR VEGETATION, CUT TREES AND GRID STUMPS WITHIN THE CLEARING LIMITS.  4. CONDUCT EARTHWORK CUTS AND FILLS.
	5. INSTALL DRAINAGE STRUCTURES AND PIPE.
$\dashv$	6. INSTALL GRAVELS FOR ACCESS DRIVE AND PARKING AREA.
	7. PLACE TOPSOIL AND SEED IN ALL AREAS OTHER THAN AREAS SURFACED WITH GRAVEL.  8. PLACE EROSION CONTROL BLANKETS ON SLOPES AS SPECIFIED ON DRAWINGS.
	9. INSTALL FENCING AND GUIDE RAILS.
	10. CLEAN UP AND REMOVE ALL CONSTRUCTION MATERIALS, EQUIPMENT, SURPLUS MATERIALS AND DEBRIS FROM PROJECT SITE.
	11. SILT FENCE TO BE REMOVED WITHIN 30 DAYS AFTER STABILIZATION OF DISTURBED AREAS.  THE CONTRACTOR SELECTED TO CONSTRUCT THIS PROJECT WILL BE RESPONSIBLE FOR IMPLEMENTATION OF SEDIMENT AND EROSION CONTROL MEASURES ON THIS SITE. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR WILL PROVIDE THE BOLTON CONSERVATION COMMISSION ENFORCEMENT OFFICERS, INLAND WETLANDS ENFORCEMENT OFFICERS, TOWN ENGINEE AND ZONING ENFORCEMENT OFFICERS WITH THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE RESPONSIBLE PERSON. SHOULD ANY PROBLEMS OCCUR, THEN THE OWNER'S AGENT SHOULD BE CONTACTED.
	CONTINGENCY PLAN
D	A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE THE OWNER'S AGENT AND THE TOWN ENGINEER WITH THE NAMES AND TELEPHONE NUMBERS OF THE RESPONSIBLE PERSONS TO BE CONTACTED IN THE EVENT OF AN EROSION AND/OR SEDIMENT CONTROL PROBLEM.
	THE CONTRACTOR SHALL AT ALL TIMES KEEP SUFFICIENT ADDITIONAL SEDIMENTATION CONTROL FENCE AND/OR HAY BALES ON THE PROJECT SITE TO CONTROL UNFORESEEN EROSION AND/OR SEDIMENT PROBLEMS. IN THE EVENT OF A PROBLEM THE CONTRACTOR SHALL PROMPTLY STABILIZE THE PROBLEM AND CONTAIN ANY SEDIMENT AND THEN NOTIFY THE OWNER'S AGENT EROSION AND SEDIMENT CONTROL
	THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF THE EROSION AND SEDIMENT CONTROL PLAN FOR THE
	PROJECT.  THE MINIMUM STANDARDS FOR ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE THOSE OUTLINED IN THE "2002
	CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL MEASURES STALL BE TROSE OF LINED IN THE 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL", LATEST REVISION. ALTERNATIVE MEASURES, METHOL MEANS AND TECHNIQUES MAY BE ALLOWED WITH THE PRIOR APPROVAL OF THE OWNER'S AGENT.
	GENERAL GUIDELINES:
	<ol> <li>NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE WITHIN AREAS DESIGNATED AS INLAND WETLANDS, WATERCOURSES OR FLOODPLAINS, DESIGNATED UPLAND REVIEW ZONES OR WITHIN STREAM CHANNEL ENCROACHMENT LINES WITHOUT ALL REQUIRED APPROVALS AND/OR PERMITS.</li> </ol>
	<ol> <li>TEMPORARY EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION.</li> <li>ALL EROSION AND SEDIMENT CONTROLS SHALL BE MAINTAINED CONTINUOUSLY AND SHALL NOT BE REMOVED UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED.</li> </ol>
	8. THE CONTRACTOR SHALL LIMIT THE DISTURBANCE OF LAND TO THOSE AREAS SHOWN ON THE DRAWINGS AND SHALL TAKE REASONABLE CARE TO PROTECT AND PRESERVE EXISTING VEGETATION WITHIN THE LIMITS OF DISTURBANCE WHERE FEASIBLE.
	9. WHERE PRACTICABLE, THE CONTRACTOR SHALL PLAN HIS CONSTRUCTION OPERATIONS SO AS TO LIMIT THE AREAS OF EXPOSED SOIL TO AREAS ACTIVELY UNDER CONSTRUCTION. THE CONTRACTOR SHALL TAKE REASONABLE CARE TO LIMIT THE PERIOD OF EXPOSURE OF DISTURBED AREAS. THE INSTALLATION OF PERMANENT VEGETATIVE MEASURES SHALL BE ACCOMPLISHED AS SOON AS IS PRACTICABLE.
	<ol> <li>ADEQUATE PROVISIONS SHALL BE TAKEN TO PROTECT ALL EXPOSED CUT AND FILL SLOPES FROM SURFACE WATER FLOW DAMAGE.</li> </ol>
	11. ALL MATERIAL FROM CLEARING AND GRUBBING OPERATIONS SHALL BE DISPOSED OF IN A LAWFUL MANNER.
С	12. WATER FROM DEWATERING OPERATIONS SHALL NOT BE DISCHARGED DIRECTLY TO ANY WETLAND OR WATERCOURSE. SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAG SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.
С	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF
С	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAG SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT (ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL
С	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT (ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING
С	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM), CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE.
С	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.
c 	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME
с _	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOAD SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FIRIBLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM, CHAY LOAM, STURES ON THE SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR
_	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FREAD LOAMY (LOAM, SANDY CLOAM, SILT LOAD SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.
C	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM). CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO
С	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAG SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT (ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.
C	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAG SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM), SANDY LOAM, SILT TOO'S SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT WE BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAG SYSTEM ONLY WHEN APPROVED, NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT CENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HICH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM), OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY EQUIPOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPLETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.  6. PREVIOUSLY ESTABLISHED GRADES ON THE AREAS TO BE TOPSOILED SHALL BE MAINTAIN
С	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAG SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AD VEHICLES SHALL TAKE PLACE IN DESIGNATED APEAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM, CHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUNDS UITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIMITABLE AFTER TILLIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPLETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY SECTION OF THE PROPER POUNT OF THE DRAWINGS.
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTICATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING, HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRISH, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS IT HALL SIDE VEIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN AND FERTILIZER.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIMIT AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL BURNOUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.  6. PREVIOUSLY ESTABLISHED GRADES ON THE AREAS TO BE TOPSOILED SHALL BE CONFINED TO THE DRAWINGS.  7. WHERE THE PHO OF THE SUBSOIL IS 6.0
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORN DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT (ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING, HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRISH, TRASH, STUMPS, ROCKS, KOOTS AND NOXIOUS WEEDS. THALL SIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPILETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.  6. PREVIOUSLY ESTABLISHED GRADES ON THE AREAS TO B
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAG SYSTEM ONLY WHEN PPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SHILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF REACH AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3358) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIRABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOA SANDY LOAV CAY LOAM, CALY LOAM). CHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SILE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN AND FERRIL ZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VARD DEPENDING ON THE SITE CONDITIONS, ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OPERATIONS.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPLETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.  6. PREVIOUSLY ESTABLISHED GRADES ON THE AREAS TO BE TOPSOILED SHALL
	SIJCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAWL SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANTARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF FOUIPMENT AND VEHICLES SHALL TAKE PLAZE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SHILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STREPPING, THEN DIVISION (750-424-3338) AND THE OWNER SHE IN THE OWNER OF THE SITE OF THE SITE OF SOIL TO SHALL BE FRIENDED AND COMPANY LOAM, SANDY LOAM, SANDY CLAY LOAM, OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS, ITSASH, STUMBE, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL BE EVEN DECEDED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZER.  INSTALLATION REQUIREMENTS  IN STALLATION REQUIREMENTS  IN STRIPPING OF TOPSOIL, SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO COPFASTIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO COPFASTIONS.  3. SIDE SLOPPES OF STOCKPILES SHALL RESULT.  3. SIDE SLOPPES OF STOCKPILES SHALL NO BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPLETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.  5. PERVOLUCIAL Y ESTABLISHED GRADES ON THE AREAS TO BE TOPSOILED SHALL BE AND THAN THE SOIL TEST TO A PHO
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. IN WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEWER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLAZE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF COOD QUALITY OF THE STET O JUSTIP'S STEPPING, HIGH QUALITY TOPSOIL SHALL BE FRIRBLE AND LOMAY (LOAM, SAMPY LOAM, SITE ION SAND). CLAY LOAM, O'LAY LOAM, O'THER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER TESTING. IT SHALL BE FREE OF DEBRIS TASAH, STUMBER, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL BE EVEN EVED EXCELED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIMIT AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEFENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO COPERATIONS.  3. SIDE SLOPES OF STOCKPILES SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR OPERATIONS.  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR OPERATIONS.  5. THE OFFICE OF THE SUBSOIL IS SOON THE SERVE OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WHITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.  6. PREVIOUSLY ESTABLISHED GRADES ON THE AREAS
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DEVARING SYSTEM.  3 THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALT TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT ENERGY AND ENVIRONMENTAL PROTECTION OL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE MYSTICATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE GITE TO JUSTIP'S TRIPPING IN 1960 MIGHT SHALL BE FRABILE AND LOWN'L (DAM SAMPY LOAM). SHAPP LOAM, THE STIT OLD STIP STRIPPING IN 1960 MIGHT SHALL BE FRABILE AND LOAMY (LOAM) SAMPY LOAM). SHAPP LOAM, FOR THE STIT OLD STIP STRIPPING IN 1976 MIGHT SHALL BE FRABILE AND LOAMY (LOAM) SAMPY LOAM). SHAPP LOAM, FOR THE STIME, IT SHALL BE FREE OF DEBRIS, TRASH STUMPS, ROCKS, ROOTS AND NOXIQUE WEEDS. IT SHALL GUYE EVIDENCE BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLAN GROWTH.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIMB AND FERTILLIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE INFORMATIVE OF THE STRIPPING OF PROPER SHALL SHORD AND AND STRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VAR DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPPRATIONS.  2. TOPSOIL SHALL BE STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIER SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BOT BE STEEPED THAN 2
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DENANGAY SYSTEM. ONLY WHEN APPROVED NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY SEVER SYSTEM.  13. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAXE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SHILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT CHERRY AND ENVIRONMENTAL PROTECTION OL AND CHEMICAL SHILL RESPONSE DIVISION (860-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FERABLE AND LOANY (LOAM, SANDY LOAM, SANDY LOAM). SHALL DO SANDY CLAY LOAM, CLAY LOAM, OTHER SHOT INTESTING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS ROCKS, ROOTS AND NOXIOUS WEEDS IT SHALL GIVE EVIDENCE BERKOWLE TO SUPPORT HEALTHY VEGETATION. IT SHALL GOVERN THE STRING. IT SHALL GIVE EVIDENCE BERKOWLE TO SUPPORT HEALTHY VEGETATION. IT SHALL GOVERN THE STRING TO SHORD AND THE SITE OLD SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME AND FERTILIZED.  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VARE DEPENDING ON THE SITE CONDITIONS, ALL SEDIMENT CONTROLS, ALL SEDIMENT DAMAGE SHALL RESULT.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OFF-SITE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARBERS SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL BE CONFINED TO STOCKPILES.  6. PREVIOUSLY YESTED AND SHALL SELFONDED ON THE SECREPAIR FROM THE PROVINCE OF PROPOSED SOURCE ON THE STRIPLING OFF-SITE SEDIMENT
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DENIANCE SYSTEM.  32 THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SHILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT - RENEW AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SHILL RESPONSE DIVISION (890-424-3336) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE STET OJ JUSTIFY STRIPPING, HIGH QUALITY TOPSOIL SHALL BE FRIBBLE AND LOANY ILOAM, SANDY LOAM, OTHER STORM. TYPES WITH HIGH GROANIC CONTENT MAY BE FOUND SUITABLE AFTER THE STING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE THE STING. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS AND NOXIOUS WEEDS. IT SHALL CAVE EVIDENCE OF SUPERIOR OF THE STING. IT SHALL CAVE EVIDENCE OF SUPERIOR OF THE STING. IT SHALL CAVE EVIDENCE OF SUPERIOR OF THE STING. IT SHALL CAVE EVIDENCE OF SUPERIOR OF THE STING. IT SHALL CAVE EVIDENCE OF SUPERIOR OF THE STING SHALL BE TORDED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIMITATION. THE STITE CONTINUE IS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  1. STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VARE DEPENDING ON THE STITE CONDITIONS, ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO OF-SHIE SEDIMENT DAMAGE SHALL RESULT.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIERS SHALL SURFACE FOR THE YEAR OF THE FORMATION OF THE STOCKPILE, IN ACCOR
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM.  3 THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAXE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAININANT SHILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT CHENRY AND ENVIRONMENTAL PROTECTION (IL AND CHEMICAL SHILL RESPONSE DIVISION (880-424-3338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE STET OJ JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FREABLE AND LOANTY LOAM, SANDY LOAM, OS THE SHALL SHALL BE FREE OF DEBRIS, TRABLE SHANDS, ROCKS, ROTER AND NO. DEVELOR. THAT IS TO TOPSOIL OF GOOD QUALITY ON THE STET OJ JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FREABLE AND LOANTY LOAM, SANDY LOAM, SA
	SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM.  31. THE STORAGE, WASHING, FUELING AND MAINTENANCE OF EQUIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAINMANT SHILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT CHENCRY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SHILL RESPONSE DIVISION (800-424-338) AND THE OWNER AGENT.  PRESERVE AND CONSERVE SOIL.  TOPSOILING  MATERIALS  SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SHE TO JUSTIFY STREPPING. HIGH QUALITY TOPSOIL SHALL BE FERRIBLE AND LOANY LOAM, SANDY LOAM, STATE OF THE SHALL BE FREED OF DEPARTMENT OF THE SHALL BE FREED OF DEPARTMENT OF THE SHALL BE FREED OF DEPARTMENT SHALL SHALL SHALL SHE WEIGHT.  ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE TROPE REPROVAL MAY VARA AND FERTILIZER.  INSTALLATION REQUIREMENTS  1. STRIPPING OF TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIMB OPERATIONS. ON THE SHALL DEPTH OF REMOVAL MAY VARA DEPENDENCE ON THE SHE TE COUNTING SHALL BE SHE DEVELOAD TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VARA DEPENDENCE ON THE SHE COOLDITIONS ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OP TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIMB OPERATIONS.  1. STRIPPING OF TOPSOIL SHALL BE CONTINUED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY VARA DEPENDENCE ON THE SHE COOLDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  2. TOPSOIL SHALL BE TESTED BY A RECOGNIZED THAT INTO THE TOTAGE SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING OPERATIONS.  3. SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.  4. A SEDIMENT BARRIERS SHALL SURROUND ALL TOPSOIL STOCKPILES.  5. TEMPORARY SEEDING OF STOCKPILES SHALL NOT BE STEEPER

COVER SURFACE WITH CRUSHED STONE OR COARSE GRAVEL. IN AREAS ADJACENT TO WATERWAYS USE CHEMICALLY

WHEN TEMPORARY DUST CONTROL MEASURES ARE USED, REPETITIVE TREATMENT SHALL BE APPLIED AS NEEDED TO

STABLE AGGREGATE

**MAINTENANCE** 

TEMPORARY SEEDING

VEGETATIVE SOIL COVER

### INSTALLATION REQUIREMENTS

SITE PREPARATION GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH

APPLICATION AND MULCH ANCHORING. ALL GRADING SHOULD BE DONE IN ACCORDANCE WITH THE REQUIREMENTS FOR 2 INSTALL NEEDED EROSION CONTROL MEASURES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, SEDIMENT BASINS AND GRASSED WATERWAY

SEEDBED PREPARATION APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS SUCH AS THOSE OFFERED BY THE UNIVERSITY OF CONNECTICUT SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVE EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE FIMING IS CRITICAL. FERTILIZER MAY BE APPLIED AT THE RATE OF 300 POUNDS PER ACRE OR 7.5 POUNDS PER 1.000 SQUARE

IET OF 10-10-10 OR EQUIVALENT. APPLY LIMESTOR DLLOWS:	NE (EQUIVALENT TO	50 PERCENT CALCIUM PLUS MAG
SOIL TEXTURE	TONS/ACRE	LBS/1,000 SQUARE FEET
CLAY, CLAY LOAM, AND HIGH ORGANIC SOIL	3	135
SANDY LOAM, LOAM, SILT LOAM	2	90
LOAMY SAND, SAND	1	45

REFER TO COUNTY SOIL SURVEY REPORT FOR SOIL TEXTURES AT THE SITE

ANNUAL RYE GRASS 40 LBS/ACRE, 1 LB/1000 SF

2. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER LIME AND SEED.

3. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDEF IYDROSEEDINGS WHICH INCLUDE MULCH, MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED BY 10 PERCENT WHEN HYDROSEEDING

4. SPRING SEEDINGS USUALLY GIVE THE BEST RESULTS, SPRING SEEDINGS OF ALL SEED LEGUMES IS RECOMMENDE HOWEVER, LATE SUMMER SEEDINGS PRIOR TO SEPTEMBER 1 CAN BE MADE. WHEN CROWN VETCH IS SEEDED IN LATE SUMMER AT LEAST 35 PERCENT OF THE SEED SHOULD BE HARD SEED (UNSCARIFIED). THE RECOMMENDED SEEDING DATES

MARCH 15 THROUGH JUNE 15 AUGUST 15 THROUGH OCTOBER 15

### PERMANENT SEEDING

INSTALLATION REQUIREMENTS

GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION EEDING, MULCH APPLICATION AND ANCHORING, AND MAINTENANCE. ALL GRADING SHOULD BE BE DONE IN ACCORDANCE WITH THE REQUIREMENTS FOR LAND GRADING.

SEEDBED PREPARATION APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TESTS SUCH AS THOSE OFFERED BY THE UNIVERSITY OF CONNECTICUT SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVI EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES. OR WHERE TIMING IS CRITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 300 POUNDS PER ACRE OR 7.5 POUNDS PER 1,000 SQUARE FEE USING 10-10-10 OR EQUIVALENT. IN ADDITION, 300 POUNDS OF 38-0-0 PER ACRE OR EQUIVALENT OF SLOW RELEASE NITROGEN MAY BE USED FOR TOPDRESSING. APPLY GROUND LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS

MAGNESIUM OXIDE) AS FOLLOWS:		
SOIL TEXTURE	TONS/ACRE	LBS/1,000 SQUARE FEET
CLAY, CLAY LOAM, AND HIGH ORGANIC SOIL	3	135
SANDY LOAM, LOAM, SILT LOAM	2	90
LOAMY SAND. SAND	1	45

AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE

REFER TO COUNTY SOIL SURVEY REPORT FOR SOIL TEXTURES AT THE SITE. IARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OR DISCING OPERATION SHALL BE ON THE GENERA CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FINE SEEDBED IS PREPARED. ALL BUT CLAY OR SILTY SOILS

3. REMOVE FROM THE SURFACE ALL STONES ONE INCH OR LARGER IN ANY DIMENSION UNLESS OTHERWISE SPECIFIED. REMOVE ALL OTHER DEBRIS SUCH AS WIRE, CABLE, TREE ROOTS, PIECES OF CONCRETE, CLODS, LUMPS OR OTHER

UNSUITABLE MATERIAL. 4. INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED, THE AREA MUST BE RETILLED AND FIRMED AS ABOVE.

SEEDING DATES 1. SPRING SEEDINGS USUALLY GIVE THE BEST RESULTS. SPRING SEEDINGS OF ALL SEED MIXES WITH LEGUMES IS RECOMMENDED, HOWEVER LATE SUMMER SEEDINGS PRIOR TO SEPTEMBER 15 CAN BE MADE. WHEN CROWN VETCH IS SEEDED IN LATE SUMMER AT LEAST 35 PERCENT OF THE SEED SHOULD BE HARD SEED (UNSCARIFIED). THE RECOMMENDED

MARCH 15 THROUGH JUNE 15 SEPTEMBER 1 THROUGH OCTOBER 15

2. WITH THE EXCEPTION OF CROWN VETCH, THE FINAL SEEDING DATE MAY BE EXTENDED 15 DAYS IN THE COASTAL TOWNS OF NEW LONDON, MIDDLESEX, NEW HAVEN AND FAIRFIELD COUNTIES

LINI ESS OTHERWISE SPECIFIED. THE SEED MIXTURE SHALL BE NEW ENGLAND CONSERVATION/WILDLIFE MIX FROM NEW INGLAND WETLAND PLANTS, INC. AMHERST, MA, OR ACCEPTED SUBSTITUTION

APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER. NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDINGS WHICH ARE MULCHED MAY BE LEFT ON SOIL SURFACE.

WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED. THE SEEDBED OWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG. SEEDING OPERATIONS SHOULD BE

4. FROST CRACK SEEDING MUST BE DONE IN LATE WINTER OR EARLY SPRING. SUITABLE WEATHER CONDITIONS ARE FREEZING NIGHTS AND THAWING DAYS WITH LITTLE OR NO SNOW COVER. SEEDING RATES MUST BE INCREASED 10 PERCENT WHEN

5. HYDRAULIC APPLICATION (HYDROSEEDING), IS A SUITABLE METHOD FOR USE ON CRITICAL AREAS. WHEN HYDROSEEDING, A SEEDBED IS PREPARED IN THE CONVENTIONAL WAY OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND TO REMOVE SURFACE STONES LARGER THAN ONE INCH IN DIAMETER. SLOPES MUST BE NO STEEPER THAN 2 TO 1 (2 FEE HORIZONTALLY TO ONE FOOT VERTICALLY). LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. THE USE OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). FIBER MULCH DOES NOT PROVIDE ADEQUATE SEEDBED PROTECTION. BETTER PROTECTION IS GAINED BY USING STRAW MULCH AND HOLDING IT WITH ADHESIVE MATERIALS OR 500 POUNDS PER ACRE OF WOOD FIBER MULCH. SEEDING RATES MUST BE

INCREASED BY 10 PERCENT WHEN HYDROSEEDING. 6. APPLY MULCH ACCORDING TO THE TEMPORARY MULCHING MEASURE.

7. IF SEEDING CANNOT BE DONE WITHIN THE SEEDING DATES, USE THE TEMPORARY MULCHING MEASURE TO PROTECT THE SITE AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD MAINTENANCE

LIME ACCORDING TO A SOIL TEST OR AT A MINIMUM OF EVERY FIVE YEARS USING A RATE OF TWO TONS PER ACRE (100 POUNDS PER 1,000 SQUARE FEET).

WHERE GRASSES PREDOMINATE, FERTILIZE ACCORDING TO A SOIL TEST OR BROADCAST BIENNIALLY, 300 POUNDS OF 10-10-10 OR EQUIVALENT PER ACRE (7.5 POUNDS PER 1,000 SQUARE FEE

WHERE LEGUMES PREDOMINATE. FERTILIZE ACCORDING TO A SOIL TEST OR BROADCAST EVERY THREE YEARS 300 POUNDS OF 0-20-20 PER ACRE OR EQUIVALENT (7.5 POUNDS PER 1,000 SQUARE FEET).

### NON-LIVING SOIL PROTECTION

### MULCH FOR SEED

MATERIALS SELECT MULCH MATERIALS BASED ON SITE CONDITIONS, AVAILABILITY OF MATERIALS AND LABOR AND EQUIPMENT. OTHER MATERIALS MAY BE USED ONLY WITH THE PERMISSION OF THE APPROVING AUTHORITY

INSTALLATION REQUIREMENTS

ORGANIC MULCHES MAY BE USED IN ANY AREA WHERE MULCH IS REQUIRED, SUBJECT TO THE RESTRICTIONS NOTED BELOW:

MULCHES PER ACRE PER 1,000 SQUARE FEET

STRAW OR HAY 1 1/2 - 2 TONS 35-45 LBS APPLICATION MULCH MATERIALS SHALL BE SPREAD UNIFORMLY, BY HAND OR MACHINE. WHEN SPREADING STRAW OR HAY MULCH B HAND, DIVIDE THE AREA TO BE MULCHED INTO APPROXIMATELY 1,000 SQUARE FOOT SECTIONS AND PLACE 35-45 POUNDS

(3/4 TO 1 BALE) OF STRAW OR HAY IN EACH SECTION TO ENSURE UNIFORM DISTRIBUTION.

HAY OR STRAW MULCHES MUST BE ANCHORED IMMEDIATELY AFTER APPLICATION TO PREVENT WINDBLOWING. HAY OR

STRAW MULCH MAY BE ANCHORED BY TRACKING WITH CONSTRUCTION EQUIPMENT, BUT NOT BY USING NETTING. MAINTENANCE

ALL MULCHES MUST BE INSPECTED PERIODICALLY, IN PARTICULAR AFTER RAINSTORMS, TO CHECK FOR RILL EROSION. WHERE EROSION IS OBSERVED, ADDITIONAL MULCH SHOULD BE APPLIED. NETS SHALL BE INSPECTED AFTER RAINSTORMS FOR DISLOCATION OR FAILURE. IF WASHOUTS OR BREAKAGE OCCUR. REINSTALL NET AS NECESSARY AFTER REPAIRING DAMAGE TO THE SLOPE. INSPECTIONS SHALL TAKE PLACE UNTIL GRASSES ARE FIRMLY ESTABLISHED. GRASSES SHALL NOT E CONSIDERED ESTABLISHED UNTIL A GROUND COVER IS ACHIEVED WHICH IS MATURE ENOUGH TO CONTROL SOIL ROSION AND TO SURVIVE SEVERE WEATHER CONDITIONS. WHERE MULCH IS USED IN CONJUNCTION WITH ORNAMENTAL PLANTINGS, INSPECT PERIODICALLY THROUGHOUT THE YEAR TO DETERMINE IF MULCH IS MAINTAINING COVERAGE OF THE

### TEMPORARY EROSION CONTROL BLANKET

A MANUFACTURED BLANKET COMPOSED OF BIODEGRADABLE/PHOTODEGRADABLE NATURAL OR POLYMER FIBERS AND/OF FILAMENTS THAT HAVE BEEN MECHANICALLY, STRUCTURALLY OR CHEMICALLY BOUND TOGETHER TO FORM A CONTINUOUS

TO PROVIDE TEMPORARY SURFACE PROTECTION TO NEWLY SEEDED AND/OR DISTURBED SOILS TO ABSORB RAINDROP IMPACT AND TO REDUCE SHEET AND RILL EROSION AND TO ENHANCE THE ESTABLISHMENT OF VEGETATION. **APPLICABILITY** 

1. ON DISTURBED SOILS WHERE SLOPES ARE 2:1 OR STEEPER.

MAY BE USED AS A SUBSTITUTE FOR TEMPORARY SOIL PROTECTION

2. WHERE WIND AND TRAFFIC GENERATED AIR FLOW MAY DISLODGE STANDARD, UNARMORED MULCHES.

4. MAY BE USE AS A SUBSTITUTE FOR MULCH FOR SEED.

PLANNING CONSIDERATION

THE SUCCESS OF TEMPORARY EROSION CONTROL BLANKETS IS DEPENDENT UPON STRICT ADHERENCE TO THE

MATERIALS

1. TEMPORARY EROSION CONTROL BLANKETS SHALL BE COMPOSED OF FIBERS AND/OR FILAMENTS THAT

A. ARE BIODEGRADABLE OR PHOTODEGRADABLE WITHIN TWO YEARS BUT WITHOUT SUBSTANTIAL DEGRADATION OVER HE PERIOD OF INTENDED USAGE (FIVE MONTHS MAXIMUM);

B. ARE MECHANICALLY, STRUCTURALLY OR CHEMICALLY BOUND TOGETHER TO FORM A CONTINUOUS MATRIX OF EVEN THICKNESS AND DISTRIBUTION THAT RESIST RAINDROP SPLASH AND WHEN USED WITH SEEDINGS ALLOW VEGETATION TO PENETRATE THE BLANKET;

C. ARE OF SUFFICIENT STRUCTURAL STRENGTH TO WITHSTAND STRETCHING OR MOVEMENT BY WIND OR WATER WHEN INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. D. ARE FREE OF ANY SUBSTANCE TOXIC TO PLANT GROWTH AND UNPROTECTED HUMAN SKIN OR WHICH INTERFERES

F. PROVIDE EITHER 80% - 95% SOIL COVERAGE WHEN USED AS A SUBSTITUTE FOR MULCH FOR SEED OR 100% INITIAL

E. CONTAIN NO CONTAMINANTS THAT POLLUTE THE AIR OR WATERS OF THE STATE WHEN PROPERLY APPLIED;

SOIL COVERAGE WHEN USED AS A SUBSTITUTE FOR TEMPORARY SOIL PROTECTION MEASURE, AND; G. DO NOT CONTAIN NETTING. 2. MATERIALS SHALL BE SELECTED AS APPROPRIATE FOR THE SPECIFIC SITE CONDITIONS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. USE OF ANY PARTICULAR TEMPORARY EROSION CONTROL BLANKET SHOULD BE SUPPORTED BY MANUFACTURER'S TEST DATA THAT CONFIRMS THE BLANKET MEETS THESE MATERIAL SPECIFICATIONS AND

WILL PROVIDE THE SHORT TERM EROSION CONTROL CAPABILITIES NECESSARY FOR THE SPECIFIC PROJECT. SITE PREPARATION AND INSTALLATION

PREPARE THE SURFACE, REMOVE PROTRUDING OBJECTS AND INSTALL TEMPORARY EROSION CONTROL BLANKETS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. ENSURE THAT THE ORIENTATION AND ANCHORING OF THE

THE BLANKET CAN BE LAID OVER AREAS WHERE SPRIGGED GRASS SEEDLINGS HAVE BEEN INSERTED INTO THE SOIL 3. WHERE LANDSCAPE PLANTINGS ARE PLANNED, LAY THE BLANKET FIRST AND THEN PLANT THROUGH THE BLANKET IN

INSPECT THE INSTALLATION TO INSURE THAT ALL LAP JOINTS ARE SECURE, ALL EDGES ARE PROPERLY ANCHORED AND ALL STAKING OR STAPLING PATTERNS FOLLOW MANUFACTURER'S RECOMMENDATIONS

INSPECT TEMPORARY EROSION CONTROL BLANKETS AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A SOILS AND/OR SEED HAVE WASHED AWAY FROM BENEATH THE BLANKET AND THE SOIL SURFACE CAN BE EXPECTED TO TINUE TO ERODE AT AN ACCELERATED RATE, AND/OR (2) THE BLANKET HAS BECOME DISLODGED SURFACE OR IS TORN.

IF WASHOUTS OR BREAKOUTS OCCUR, RE-INSTALL THE BLANKET AFTER REGRADING AND RE-SEEDING, ENSURING THA BLANKET INSTALLATION STILL MEETS DESIGN SPECIFICATIONS. WHEN REPETITIVE FAILURES OCCUR AT THE SAME LOCATION. REVIEW CONDITIONS AND LIMITATIONS FOR USE AND DETERMINE IF DIVERSIONS, STONE CHECK DAMS OR OTHER MEASURES ARE NEEDED TO REDUCE FAILURE RATE.

REPAIR ANY DISLODGED OR FAILED BLANKETS IMMEDIATELY. 4. WHEN USED AS A SUBSTITUTE FOR MULCH FOR SEED, CONTINUE TO INSPECT AS REQUIRED BY THE SEEDING MEASURE.

WHEN USED AS A SUBSTITUTE FOR TEMPORARY SOIL PROTECTION. CONTINUE TO INSPECT UNTIL IT IS REPLACED BY OTHER

### PERMANENT TURF REINFORCEMENT MAT

EROSION CONTROL MEASURES OR UNTIL WORK RESUMES.

1. A MANUFACTURED MAT COMPOSED OF NON-BIODEGRADABLE POLYMER OR SYNTHETIC FIBERS MECHANICALLY, STRUCTURALLY OR CHEMICALLY BOUND TOGETHER TO FORM A CONTINUOUS MATRIX

1. TO PROVIDE PERMANENT TURF REINFORCEMENT WHERE DESIGN FLOWS EXCEED THE STABILITY OF THE SOILS AND/OR PROPOSED VEGETATION.

2. TO ENHANCE THE ESTABLISHMENT OF VEGETATION AS THE FINAL SURFACE PROTECTION. APPLICABILITY

IN CHANNELS WHERE DESIGN VELOCITIES EXCEED THE STABILITY LIMITS OF THE SOIL AND/OR VEGETATION, AND A SOFT-ARMORED APPROACH IS DESIRED.

2. ON UNSTABLE SOILS WHERE INTERMITTENT FLOW EXISTS.

3. ON DISTURBED SOILS WITH SLOPES 2:1 OR FLATTER. ON SHORELINES ABOVE A PROTECTED OR STABLE TOE TO REDUCE SOIL EROSION.

PLANNING CONSIDERATIONS

1. AS A RULE OF THUMB, WHEN FLOWS OVER EXPOSED SOILS EXCEED 2 FEET PER SECOND AND FLOWS OVER PROPOSED TURF REAS EXCEED 5-6 FEET PER SECOND, THEN SOIL EROSION CAN BE EXPECTED

WHERE TURF REINFORCEMENT MATS ARE USED IN AREAS OF CONCENTRATED FLOWS AN ENGINEERED DESIGN IS REQUIRED. FOR OTHER APPLICATIONS REFER TO THE MANUFACTURER'S RECOMMENDATIONS MATERIAL

PERMANENT TURF REINFORCEMENT MATS SHALL:

1. CONSIST OF ULTRAVIOLET LIGHT RESISTANT POLYMER OR SYNTHETIC FIBERS MECHANICALLY, STRUCTURALLY, AND/OR CHEMICALLY BOUND TOGETHER FOR A CONTINUOUS MATRIX OF CONSISTENT THICKNESS; CONTAIN NO CONTAMINANTS THAT POLLUTE THE AIR OR WATERS OF THE STATE WHEN PROPERLY INSTALLED: AND BE FREE

OF ANY SUBSTANCE TOXIC TO PLANT GROWTH AND UNPROTECTED HUMAN SKIN OR WHICH INTERFERES WITH SEED

MATERIALS SHALL BE SELECTED AS APPROPRIATE FOR THE SPECIFIC SITE CONDITIONS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. USE OF ANY PARTICULAR PERMANENT TURE REINFORCEMENT MAT SHOULD BE

SUPPORTED BY MANUFACTURER'S TEST DATA THAT CONFIRMS THE MAT WILL PROVIDE THE LONG TERM EROSION CONTROL APARII ITIFS NECESSARY FOR THE SPECIFIC PROJECT, AND DO NOT CONTAIN NETTING.

**INSTALLATION REQUIREMENTS** 

PREPARE SITE AND INSTALL IN ACCORDANCE WITH MANUFACTURER'S REQUIREMENTS. ESTABLISH VEGETATIVE COVER IN ACCORDANCE WITH THESE GUIDELINES. MODIFY THE SEQUENCE OF APPLICATION TO MEET THE MANUFACTURER'S REQUIREMENTS FOR THE SPECIFIC INSTALLATION.

INSPECT THE INSTALLATION TO ENSURE THAT THE MAT IS IN DIRECT CONTACT WITH THE PREPARED SOIL SURFACE, ALL LAP JOINTS ARE SECURE, ALL EDGES AND INTERIOR MATS ARE PROPERLY ANCHORED AND/OR TREATED, BACKFILLING FOLLO. THE MANUFACTURER'S REQUIREMENTS, AND THE VEGETATIVE SOIL MEASURES USED HAVE BEEN CORRECTLY APPLIED.

INSPECT PERMANENT TURF REINFORCEMENT MATS AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL AMOUNT OF 0.5 INCH OR GREATER FOR FAILURES UNTIL THE TURF HAS BECOME ESTABLISHED. MAT FAILURE HAS OCCURRED WHEN SOILS AND/OR SEED HAVE WASHED AWAY FROM BENEATH OR WITHIN THE MAT RESULTING IN A SOIL SURFACE THAT CAN BE EXPECTED TO CONTINUE TO ERODE OR WHEN THE MAT HAS BECOME DISLODGED FROM THE SOIL SURFACE. WHEN REPETITIVE FAILURES OCCUR AT THE SAME LOCATION, REVIEW CONDITIONS AND LIMITATIONS OF TURF REINFORCEMENT MATS AND DETERMINE IF ADDITIONAL CONTROLS, (E.G. DIVERSIONS, STONE BARRIERS) ARE NEEDED ENSURE SUCCESS. REPAIR MAT FAILURES WITHIN ONE WORK DAY

2. AFTER THE TURF HAS BECOME ESTABLISHED, INSPECT ANNUALLY OR AFTER MAJOR STORM EVENTS.

### **ENERGY DISSIPATORS**

STONE CHECK DAM DEFINITION

1. A TEMPORARY STONE DAM PLACED ACROSS A DRAINAGEWAY

1. TO REDUCE THE VELOCITY OF CONCENTRATED STORM WATER FLOWS, THEREBY REDUCING EROSION OF THE

2. TO TEMPORARILY POND STORM WATER RUNOFF TO ALLOW SEDIMENTS TO SETTLE OUT. APPLICABILITY

WHERE CONCENTRATED FLOWS ARE EXPECTED TO CAUSE EROSION

FOR TEMPORARY DRAINAGEWAYS WHICH, BECAUSE OF THEIR SHORT LENGTH OF SERVICE, WILL NOT RECEIVE A NON-ERODABLE LINING BUT STILL NEED PROTECTION TO REDUCE EROSION. FOR PERMANENT DRAINAGEWAYS WHICH, FOR SOME REASON, WILL NOT RECEIVE A PERMANENT NON-ERODABLE LINING FOR AN EXTENDED PERIOD OF TIME.

4. FOR TEMPORARY OR PERMANENT DRAINAGEWAYS WHICH NEED PROTECTION DURING THE ESTABLISHMENT OF VEGETATIVE LININGS. THIS MEASURE IS NOT A SUBSTITUTE FOR A TEMPORARY SEDIMENT TRAP OR A TEMPORARY SEDIMENT BASIN, HOWEVER, STONE CHECK DAMS MAY BE USED IN CONJUNCTION WITH THOSE MEASURES. PLANNING CONSIDERATIONS

1. A STONE CHECK DAM IS CONSIDERED TO BE TEMPORARY IF IT IS USED LESS THAN 1 YEAR. IT IS CONSIDERED TO BE

PERMANENT IF IT IS USED MORE THAN 1 YEAR. DESIGN REQUIREMENTS DRAINAGE AREA LENGTH OF USE NO ENGINEERED DESIGN <6 MONTHS < OR = 2 ACRES 6 MONTHS TO <1 YEAR 2-YR FREQUENCY STORM >2 ACRES 25-YR FREQUENCY STORM ANY DRAINAGE SIZE

FOR USE OF A STONE CHECK DAM LESS THAN 1 YEAR, DESIGN THE STONE CHECK DAM TO SAFELY PASS THE PEAK FLOW EXPECTED FROM A 2-YEAR FREQUENCY STORM WITHOUT STRUCTURAL FAILURE AND ADVERSE TAILWATER EFFECTS. FOR USE OF A STONE CHECK DAM EXCEEDING 1 YEAR, DESIGN THE STONE CHECK DAM TO SAFELY PASS THE PEAK FLOW EXPECTED FROM A 25-YEAR FREQUENCY STORM WITHOUT STRUCTURAL FAILURE OF THE CHECK DAM AND ADVERSE

SPECIFICATIONS

DESIGN CRITERIA

FOR ENGINEERED STONE CHECK DAMS, CONSTRUCT THE STONE CHECK DAM IN ACCORDANCE WITH THE DESIGN STANDARDS AND SPECIFICATIONS. FOR ALL NON-ENGINEERED STONE CHECK DAMS, COMPLY WITH THE FOLLOWING

1. STONE: SHALL MEET THE REQUIREMENTS OF DOT STANDARD SPECIFICATIONS SECTION M.01.01, 2" CRUSHED STONE. THE STONE SHALL BE SOUND, TOUGH, DURABLE, ANGULAR, NOT SUBJECT TO DISINTEGRATION ON EXPOSURE TO WATER OR WEATHERING, BE CHEMICALLY STABLE, AND SHALL BE SUITABLE IN ALL OTHER RESPECTS FOR THE PURPOSE INTENDED. PLACE THE STONE BY HAND OR MACHINE, MAKING THE SIDE SLOPES NO STEEPER THAN 1.5:1 (I.E., THE ANGLE OF REPOSE) WITH A MAXIMUM HEIGHT OF 3 FEET AT THE CENTER OF THE CHECK DAM. A GEOTEXTILE MAY BE USED UNDER THE STONE

ROVIDE A STABLE FOUNDATION AND TO FACILITATE REMOVAL OF THE STON

SHALL NOT EXCEED 3 FEET IN HEIGHT AT THE CENTER. EXTEND THE STONE CHECK DAM TO THE FULL WIDTH OF THE DRAINAGEWAY, PLUS 18 INCHES ON EACH SIDE LEAVING THE HEIGHT OF THE CENTER OF THE STONE CHECK DAM XIMATELY 6 INCHES LOWER THAN THE HEIGHT OF THE OUTER EDGE 3. THE MAXIMUM SPACING BETWEEN CHECK DAMS SHALL BE SUCH THAT THE TOE OF THE UPSTREAM CHECK DAM IS AT THE SAME ELEVATION AS THE TOP OF THE CENTER OF THE DOWNSTREAM CHECK DAM.

IN DRAINAGEWAYS: THE MINIMUM HEIGHT OF THE CHECK DAM SHALL BE THE FLOW DEPTH OF THE DRAINAGEWAY BUT IT

4. CATCH BASINS IN DRAINAGEWAYS ON SLOPES AND AT CULVERT INLETS: WHERE CATCH BASINS IN DRAINAGEWAYS ARE OCATED ON SLOPES OR AT CULVERT INLETS, LOCATE THE CHECK DAM ACROSS THE DRAINAGEWAY NO FARTHER THAN FEET ABOVE THE CATCH BASIN OR CULVERT. FOR CULVERT INLETS, LOCATE THE CHECK DAM AT LEAST 6 FEET FROM THE

CATCH BASINS IN DEPRESSIONS OR LOW SPOTS (YARD DRAINS): ENCIRCLE THE ENTIRE CATCH BASIN WITH A STONE CHECK DAM NOT TO EXCEED 18 INCHES IN HEIGHT AND 3 FEET OUT FROM THE OUTSIDE EDGE OF THE TOP OF THE FRAME.

CULVERT INLETS: LOCATE THE STONE CHECK DAM APPROXIMATELY 6 FEET FROM THE CULVERT IN THE DIRECTION OF THE INCOMING FLOW.

MAINTENANCE

FOR PERMANENT STONE CHECK DAMS. INSPECT AND MAINTAIN THE STONE CHECK DAM IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS PROVIDED IN THE DESIGN.

FOR TEMPORARY STONE CHECK DAMS. INSPECT STONE CHECK DAMS AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL AMOUNT OF 0.5 INCH OR GREATER TO DETERMINE MAINTENANCE NEEDS.

3. REMOVE THE SEDIMENT DEPOSITS WHEN DEPOSITS REACH APPROXIMATELY HALF THE HEIGHT OF THE CHECK DAM. 4. REPLACE OR REPAIR THE CHECK DAM WITHIN 24 HOURS OF OBSERVED FAILURE. FAILURE OF THE CHECK DAM HAS OCCURRED WHEN SEDIMENT FAILS TO BE RETAINED BECAUSE A. STONE HAS MOVED,

B. SOIL HAS ERODED AROUND OR UNDER THE CHECK DAM REDUCING ITS FUNCTIONAL CAPACITY, OR TRAPPED SEDIMENTS ARE OVERTOPPING THE CHECK DAM. WHEN REPETITIVE FAILURES OCCUR AT THE SAME LOCATION, REVIEW CONDITIONS AND LIMITATIONS FOR USE AND

DETERMINE IF ADDITIONAL CONTROLS (E.G. TEMPORARY STABILIZATION OF CONTRIBUTING AREA, DIVERSIONS, STONE CHECK DAMS) ARE NEEDED TO REDUCE FAILURE RATE. MAINTAIN THE STONE CHECK DAM UNTIL THE CONTRIBUTING AREA IS STABILIZED.

AFTER THE CONTRIBUTING AREA IS STABILIZED. REMOVE ACCUMULATED SEDIMENT, STONE CHECK DAMS MAY BE REMOVED.

OR GRADED INTO THE FLOW LINE OF THE CHANNEL OVER THE AREA LEFT DISTURBED BY SEDIMENT REMOVAL. GRADE SO

THERE ARE NO OBSTRUCTIONS TO WATER FLOW. IF STONE CHECK DAMS ARE USED IN GRASS-LINED CHANNELS WHICH WILL BE MOWED, REMOVE ALL THE STONE OR CAREFULLY GRADE OUT THE STONE TO ENSURE IT DOES NOT INTERFERE WITH 8. STABILIZE ANY DISTURBED SOIL THAT REMAINS FROM CHECK DAM REMOVAL OPERATIONS.

OUTLET PROTECTION

STRUCTURALLY LINED APRONS OR OTHER ACCEPTABLE ENERGY DISSIPATING DEVICES PLACED BETWEEN THE OUTLETS OF PIPES OR PAVED CHANNEL SECTIONS AND A STABLE DOWNSTREAM CHANNEL.

TO PREVENT SCOUR AT STORM DRAIN, CULVERT OR DRAINAGEWAY OUTLETS AND TO MINIMIZE THE POTENTIAL FOR DOWNSTREAM EROSION BY REDUCING THE VELOCITY OF CONCENTRATED STORM WATER FLOWS.

AT THE OUTFALL OF ALL STORM DRAIN OUTLETS, ROAD CULVERTS, PAVED CHANNEL OUTLETS, NEW CHANNELS CONSTRUCTED AS OUTLETS FOR CULVERTS AND CONDUITS. ETC. DISCHARGING INTO NATURAL OR CONSTRUCTED CHANNELS, WHICH IN TURN DISCHARGE INTO EXISTING STREAMS OR DRAINAGE SYSTEMS. PLANNING CONSIDERATIONS

ANALYSIS AND APPROPRIATE TREATMENT SHALL BE DONE ALONG THE ENTIRE LENGTH OF THE FLOW PATH FROM THE END OF THE CONDUIT, CHANNEL OR STRUCTURE TO THE POINT OF ENTRY INTO AN EXISTING STREAM OR PUBLICLY MAINTA PRAINAGE SYSTEM. WHERE FLOW IS EXCESSIVE FOR THE ECONOMICAL USE OF AN APRON, EXCAVATED STILLING BASINS DESIGN CRITERIA

DETERMINATION OF NEEDS. THE NEED FOR CONDUIT OUTLET PROTECTION SHALL BE DETERMINED BY COMPARING THE ALLOWABLE VELOCITY WHICH THE SOIL WILL WITHSTAND TO THE EXIT VELOCITY OF THE FLOW FROM THE CONDUIT. THE ALLOWABLE VELOCITY FOR WATER OVER THE SOIL SHALL BE THAT GIVEN IN FIGURE OP-1 BELOW. THE EXIT VELOCITY OF THE WATER IN THE CONDUIT SHALL BE CALCULATED USING THE GREATER OF THE CONDUIT DESIGN STORM OR THE 25-YEAR FREQUENCY STORM. WHEN THE EXIT VELOCITY OF THE WATER IN THE CONDUIT EXCEEDS THE ALLOWABLE VELOCITY FOR IE SOIL, OUTLET PROTECTION IS REQUIRED. OUTLET PROTECTION IS ALSO REQUIRED IF THE CONDUIT OUTFALL IS SE ABOVE THE RECEIVING CHANNEL (I.E., CANTILEVERED) CAUSING THE WATER TO DROP AT THE OUTLET END OF THE CULVERT.

FIGURE OP-1 ALLOWABLE VELOCITIES FOR VARIOUS SOILS SOIL TEXTURE ALLOWABLE VELOCITY (FT./SEC.) SAND AND SANDY LOAM SILT LOAM SANDY CLAY LOAM CLAY LOAM CLAY, FINE GRAVEL, GRADED LOAM TO SOIL

OTHER OUTLET PROTECTIONS

RIPRAP APRONS

. DESIGN LIMITATIONS: NO BENDS OR CURVES AT THE INTERSECTION OF THE CONDUIT AND THE APRON PROTECTION WILL BE 2. THERE SHALL BE NO VERTICAL DROP FROM THE END OF THE APRON TO THE RECEIVING CHANNEL.

STANDARD ENGINEERING PRACTICES ALLOW FOR MANY DIFFERENT TYPES OF OUTLET PROTECTION WHICH PROVID ENERGY DISSIPATION. COMMON OUTLET PROTECTIONS INCLUDE THE USE OF A RIPRAP APRON AND A RIPRAP STILLING

INSTALLATION REQUIREMENTS

MAINTENANCE INSPECT THE COMPLETED STRUCTURE ANNUALLY AND AFTER EACH MAJOR RAINFALL FOR DAMAGE AND DETERIORATION.

LEVEL SPREADER

AN OUTLET FOR DIVERSIONS AND OTHER WATER CONVEYANCES CONSISTING OF AN EXCAVATED DEPRESSION WITH A BROAD STABLE POINT OF DISCHARGE CONSTRUCTED AT ZERO GRADE ACROSS A SLOPE TO REDUCE THE DEPTH AND VELOCITY OF CONCENTRATED RUNOFF AND RELEASE IT UNIFORMLY AS SHEET FLOW ONTO A

**APPLICABILITY** WHERE THERE IS A NEED TO CARRY STORM WATER AWAY FROM DISTURBED AREAS AND TO AVOID STRESSING EROSION

3. WHERE THE SPREADER CAN BE CONSTRUCTED ON UNDISTURBED SOIL. 4. WHERE THE AREA BELOW THE LEVEL SPREADER LIP HAS A SLOPE OF 5% OR FLATTER AND IS STABILIZED BY VEGETATION.

PLANNING CONSIDERATIONS 1. THE TEMPORARY DIVERSION MEASURE AND THE WATER BAR MEASURE EACH CALLS FOR A STABLE OUTLET FOR NCENTRATED STORM WATER FLOWS. THE LEVEL SPREADER IS A RELATIVELY LOW-COST STRUCTURE TO RELEASE SMALL

WHERE SEDIMENT REDUCED RUNOFF CAN BE RELEASED IN SHEET FLOW OVER A STABILIZED SLOPE WITHOUT CAUSING

OLUMES OF CONCENTRATED FLOW WHERE SITE CONDITIONS ARE SUITABLE 2. CHECK THE PROPOSED LOCATION OF THE LEVEL SPREADER TO ENSURE IT CAN BE CONSTRUCTED ON LEVEL, STABLE, AND UNDISTURBED GROUND. ANY DEPRESSIONS IN THE OUTLET LIP OF THE SPREADER COULD CONCENTRATE FLOW, AND RESULT IN EROSION. CHECK CONDITIONS DOWNSLOPE FORM THE SPREADER TO ENSURE THE RUNOFF WATER WILL NOT RECONCENTRATE AFTER RELEASE UNLESS IT OCCURS DURING INTERCEPTION BY ANOTHER MEASURE (SUCH AS A PERMANENT POND OR DETENTION BASIN) LOCATED BELOW THE LEVEL SPREADER.

3. FOR HIGHER DESIGN FLOW CONDITIONS, A RIGID OUTLET LIP DESIGN IS REQUIRED TO ENSURE THE DESIRED SHEET FLOW 4. SPECIAL CARE SHALL BE TAKEN WHEN DESIGNING LEVEL SPREADERS ON TERRACE ESCARPMENTS LOCATED IN THE CONNECTICUT RIVER VALLEY. THESE AREAS ARE VERY SUSCEPTIBLE TO EROSION BY THE CONCENTRATION FLOWS. CONSIDER USING ALTERNATIVE METHODS TO DISCHARGE RUNOFF THROUGH THE ESCARPMENT AREA.

**DESIGN CRITERIA** SLOPES SHALL BE SUFFICIENTLY SMOOTH TO PRESERVE SHEET FLOW AND PREVENT FLOW FROM CONCENTRATING. CRITERIA PROVIDED BELOW ARE FOR FLOWS FROM A 10-YEAR FREQUENCY STORM THAT IS EQUAL TO OR LESS THAN 20 CFS (Q10 < 20 CFS). FOR HIGHER FLOWS USE OTHER STANDARD ENGINEERING PRACTICES THAT WILL RESULT IN A DIFFUSE NON-EROSIVÉ DISCHARGE.

1. DETERMINE THE SIZE OF THE LEVEL SPREADER BY ESTIMATING THE PEAK FLOW EXPECTED FROM A 10-YEAR STORM (Q10). 2. SELECT THE APPROPRIATE LENGTH, WIDTH AND DEPTH OF THE SPREADER FROM TABLE LS-1 BELOV 3. PROVIDE A 20-FOOT TRANSITION SECTION IN THE DIVERSION CHANNEL SO THAT THE WIDTH OF THE DIVERSION WILL

SMOOTHLY TRANSITION WITH THE WIDTH OF THE SPREADER TO ENSURE MORE UNIFORM OUTFLOW. 4. MAKE THE DEPTH OF THE LEVEL SPREADER, AS MEASURED FROM THE LIP, AT LEAST 6 INCHES. THE DEPTH MAY BE MADE GREATER TO INCREASE TEMPORARY STORAGE CAPACITY, IMPROVE TRAPPING OF DEBRIS AND TO ENHANCE SETTLING OF

TABLE LS-1 MINIMUM DIMENSIONS FOR LEVEL SPREADER DESIGN FLOW, Q10 (CFS) DEPTH (FT.) WIDTH OF LOWER SIDE SLOPE SPREADER (FT.) LENGTH (FT.)

1. THE GRADE OF THE CHANNEL FOR THE LAST 20 FEET OF THE DIKE OR DIVERSION ENTERING THE LEVEL SPREADER SHALL BE 2. THE GRADE OF THE LEVEL SPREADER CHANNEL SHALL BE 0.0%.

THE LEVEL LIP OF THE SPREADER SHALL BE OF UNIFORM HEIGHT AND ZERO GRADE OVER THE LENGTH OF THE SPREADEF

A VEGETATED LEVEL LIP SHALL BE CONSTRUCTED WITH AN EROSION-RESISTANT MATERIAL, SUCH AS PERMANENT TURF

WITH ITS DISCHARGE TO AN UNDISTURBED WELL-VEGETATED AREA HAVING A MAXIMUM SLOPE OF 5%. SLOPES SHALL BE SUFFICIENTLY SMOOTH TO PRESERVE SHEET FLOW AND PREVENT FLOW FROM CONCENTRATING. 2. THE LEVEL SPREADER LIP MAY BE STABILIZED BY VEGETATION OR MAY BE OF A RIGID NON-ERODIBLE MATERIAL DEPENDING

REINFORCEMENT MATTING OR TEMPORARY EROSION CONTROL BLANKETS. TO INHIBIT EROSION AND ALLOW VEGETATION TO I. FOR HIGHER DESIGN FLOWS AND PERMANENT INSTALLATIONS, A RIGID LIP OF NON-ERODIBLE MATERIAL, SUCH AS

SPREADER LIP DESIGN FLOW (CFS)

FIGURE LS-2 <u>DISCHARGE LIMITATION</u>

SPREADER DIMENSIONS

SPREADER LIF

VEGETATED

INSTALLATION REQUIREMENTS CONSTRUCT THE LEVEL SPREADER ON UNDISTURBED SOIL (NOT FILL MATERIAL).

CONSTRUCT A 20-FT. LONG TRANSITION SECTION FROM THE DIVERSION CHANNEL TO BLEND SMOOTHLY TO THE WIDTH AND DEPTH OF THE SPREADER.

4. CONSTRUCT THE LEVEL LIP AT 0.0% GRADE TO ENSURE UNIFORM SPREADING OF STORM WATER RUNOFF FLOW. THE PROTECTIVE COVERING FOR A VEGETATED LIP SHALL BE A MINIMUM OF 4 FEET WIDE EXTENDING 6 INCHES OVER THI

SHAPE THE ENTRANCE TO THE SPREADER IN SUCH A MANNER AS TO ENSURE THAT RUNOFF ENTERS DIRECTLY ONTO THI

LIP AND BURIED 6 INCHES DEEP IN A VERTICAL TRENCH ON THE LOWER EDGE. BUTT THE UPPER SMOOTHLY CUT SOD, AND SECURELY HOLD IN PLACE WITH CLOSELY SPACED HEAVY DUTY WIRE STAPLES. ENTRENCH THE RIGID LEVEL LIP AT LEAST 2 INCHES BELOW EXISTING GROUND AND SECURELY ANCHOR TO PREVENT DISPLACEMENT, PLACE AN APRON OF DOT 2" CRUSHED STONE OR MODIFIED RIPRAP AT THE TOP OF THE LEVEL LIP AND EXTENDED DOWN SLOPE AT LEAST 3 FEET. PLACE THE GEOTEXTILE UNDER STONE AND USE GALVANIZED WIRE MESH TO

STABILIZE THE DISTURBED AREA AROUND THE SPREADER IMMEDIATELY AFTER ITS CONSTRUCTION (SEE PERMANENT SEED, MULCH FOR SEED AND/OR STONE SLOPE PROTECTION MEASURES). MAINTENANCE

FOR TEMPORARY INSTALLATIONS, INSPECT THE LEVEL SPREADER AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL AMOUNT OF 0.5 INCH OR GREATER TO DETERMINE MAINTENANCE NEEDS

FOR PERMANENT INSTALLATIONS, INSPECT AFTER MAJOR RAINSTORMS OR ONCE A YEAR.

MAINTAIN THE LEVEL SPREADER LIP AT 0.0% SLOPE TO ALLOW FOR PROPER FUNCTIONING OF THE MEASURE. AVOID THE PLACEMENT OF ANY MATERIAL ON AND PREVENT CONSTRUCTION TRAFFIC ACROSS THE STRUCTURE. IF THE MEASURE IS DAMAGED BY CONSTRUCTION TRAFFIC, REPAIR IT IMMEDIATELY.

SEDIMENT IMPOUNDMENTS, BARRIERS, AND FILTERS

HAY BALE BARRIER

FLOWING BETWEEN THE BALES.

HOLD STONE SECURELY IN PLACE.

INSTALLATION REQUIREMENTS

SHEET FLOW APPLICATIONS BALES SHALL BE PLACED IN A SINGLE ROW, LENGTHWISE ON THE CONTOUR, WITH THE ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER

ALL BALES SHALL BE EITHER WIRE-BOUND OR STRING TIED. BALES SHALL BE INSTALLED SO THAT BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES TO PREVENT DETERIORATION OF THE

OF 4 INCHES. AFTER THE BALES ARE STAKED AND CHINKED, THE EXCAVATED SOIL SHALL BE BACKFILLED AGAINST THE BARRIER BACKELL SOIL SHALL CONFORM TO THE GROUND LEVEL ON THE DOWNHILL SIDE AND SHALL BE BUILT LIP TO 4 CHES AGAINST THE UPHILL SIDE OF THE BARRIER. BALES SHOULD BE PLACED 10 FEET AWAY FROM THE TOE OF SLOPES UNLESS OTHERWISE SHOWN ON THE DRAWINGS OR DIRECTED.

A TRENCH SHALL BE EXCAVATED THE WIDTH OF A BALE AND THE LENGTH OF THE PROPOSED BARRIER TO A MINIMUM DEPTH

EACH BALE SHALL BE SECURELY ANCHORED BY AT LEAST TWO STAKES DRIVEN THROUGH THE BALE. THE FIRST STAKE IN

EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE TO FORCE THE BALES TOGETHER. STAKES SHALL BE DRIVEN DEEP ENOUGH INTO THE GROUND TO SECURELY ANCHOR THE BALES. THE GAPS BETWEEN BALES SHALL BE CHINKED (FILLED BY WEDGING) STRAW BETWEEN THEM TO PREVENT WATER FROM

CHANNEL FLOW APPLICATIONS BALES SHALL BE PLACED IN A SINGLE ROW, LENGTHWISE, ORIENTED PERPENDICULAR TO THE CONTOUR, WITH ENDS OF DJACENT BALES TIGHTLY ABUTTING ONE ANOTHER

FOLLOWING ADDITION: THE BARRIER SHALL BE EXTENDED TO SUCH A LENGTH THAT THE BOTTOMS OF THE END BALES ARE HIGHER IN ELEVATION THAN THE TOP OF THE LOWEST MIDDLE BALE TO ASSURE THAT SEDIMENT LADEN RUNOFF WILL FLOW EITHER THROUGH OF

THE REMAINING STEPS FOR INSTALLING A BALE BARRIER FOR SHEET FLOW APPLICATIONS APPLY HERE, WITH THE

INSPECTION SHALL BE MADE AFTER EACH STORM EVENT AND PERIODICALLY DURING PROLONGED RAIN EVENTS AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED

GEOTEXTILE, GEOTEXTILE SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON, POLYESTER OR ETHYLENE FILAMENTS AND

50 LBS./LIN. IN. (MIN)

30 LBS./LIN. IN. (MIN)

HALL BE CERTIFIED BY THE MANUFACTURER OR SUPPLIER AS CONFORMING TO THE FOLLOWING REQUIREMENT

2. ACCUMULATED SEDIMENT BEHIND THE BALES SHALL BE REMOVED WHEN IT REACHES 1/2 OF THE ORIGINAL HEIGHT OF THE

GEOTEXTILE SILT FENCE MATERIALS

EXTRA STRENGTH

MAINTENANCE

REPLACEMENT SHALL BE MADE AS REQUIRED.

STANDARD STRENGTH

REQUIREMENTS FILTERING EFFICIENCY 75% (MIN)

TENSILE STRENGTH AT 20% (MAX) ELONGATION

12 GAL./SF/MIN. (MIN.) STAKES FOR GEOTEXTILE SILT FENCES SHALL BE 1" x 1" WOOD WITH A MINIMUM LENGTH OF 5 FEET

3. WIRE FENCE REINFORCEMENT FOR GEOTEXTILE SILT FENCES USING STANDARD STRENGTH MATERIAL SHALL BE A MINIMUM

OF 42 INCHES IN HEIGHT, A MINIMUM OF 14 GAUGE AND SHALL HAVE A MAXIMUM MESH SPACING OF 6 INCHES. THE HEIGHT OF THE BARRIER SHALL NOT EXCEED 36 INCHES. (HIGHER BARRIERS MAY IMPOUND VOLUMES OF WATER

SUPPLICIENT TO CAUSE FAILURE OF THE STRUCTURE). THE SEDIMENTATION CONTROL FENCE SHALL BE PLACED 10 FEE AWAY FROM THE TOE OF SLOPES UNLESS OTHERWISE SHOWN ON THE DRAWINGS OR DIRECTED. WHEN JOINTS ARE NECESSARY, GEOTEXTILE ROLL ENDS SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6" OVERLAP AND SECURELY SEALED IN CONFORMANCE WITH THE MANUFACTURERS RECOMMENDATIONS.

WHEN STANDARD STRENGTH GEOTEXTILE IS USED, A WIRE MESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST 1 INCH LONG, TIE WIRES OR HOG RINGS. THE WIRE SHALL EXTEND INTO A TRENCH A MINIMUM OF 2 INCHES AND SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE

POSTS SHALL BE SPACED A MAXIMUM OF 10 FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM DEPTH OF 12

INSPECTION SHALL BE MADE AFTER EACH STORM EVENT AND PERIODICALLY DURING PROLONGED RAINFALL. REPAIR OR

2. ACCUMULATED SEDIMENT BEHIND THE FENCE SHALL BE REMOVED WHEN IT REACHES 1/2 OF THE HEIGHT OF THE BARRIER

ORIGINAL GROUND SURFACE. THE STANDARD STRENGTH GEOTEXTILE SHALL BE STAPLED, WIRED OR TIED TO THE WIRE FENCE, AND 8 INCHES OF THE GEOTEXTILE SHALL BE EXTENDED INTO THE TRENCH.

WHEN EXTRA STRENGTH GEOTEXTILE OR BURLAP AND CLOSER POST SPACING ARE USED, THE WIRE MESH SUPPORT FENCE 7. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE GEOTEXTILE

**EROSION AND** SEDIMENT CONTROL **NOTES** 

HIS DRAWING IS INTENDED TO BE USED FOR INFORMATION AND REVIEW

URPOSES ONLY AND IS NOT INTENDED TO BE USED FOR CONSTRUCTION

TOWN OF BOLTON.

CONNECTICUT

HERRICK MEMORIAL

PERMITTING

ANY ALTERATIONS TO THIS DRAWING MADE WITHOUT THE EXPRESSE VRITTEN APPROVAL OF NATHAN L. JACOBSON & ASSOCIATES, INC. WILL B T THE SOLE RISK OF THE PERSON OR FIRM MAKING SUCH UNAUTHORIZ ALTERATIONS AND NATHAN L. JACOBSON & ASSOCIATES, INC. WILL NEITHEF HAVE NOR ACCEPT ANY LIABILITY OR LEGAL EXPOSURE ARISING FROM SAI

UNAUTHORIZED ALTERATIONS.



NOTES:

SEE PROJECT NOTES SHEET 7

Nathan L. Jacobson & Associates, Inc. 86 Main Street P.O. Box 337 Chester, Connecticut 06412-0337 Tel: (860) 526-9591 Fax: (860) 526-5416 www.nlja.com Jacobson Consulting Civil and Environmental Engineers Since 1972


NOT VALID WITHOUT ORIGINAL SEAL JOSEPH M. DILLON, P.E.

> © COPYRIGHT 2025 NATHAN L. JACOBSON & ASSOCIATES INC. ALL RIGHTS RESERVED.


CT REGISTRATION No. 22903


	REVISIONS	
No.	DESCRIPTION	DATE

SHEET No.:	OCTOBER 2025	DATE:
	NONE	SCALE:
	09630011	PROJECT No.:
5 OF 8	09630011ED	CADD FILE:
JOF	JMD	DESIGNED:
	TPH	DRAWN:
		CHECKED.



I:\Civil 3D\09630011_Production Drawings\Permitting\09630011ED.dwg, 10/21/2025 11:33:56 AM, AutoCAD PDF (General Documentation)





### **Abutting Property Owners**

SUITOR NICOLE D & EARL	42 CLARK RD	BOLTON, CT 06043
CARROLL BIJOUR	54 CLARK RD	BOLTON, CT 06043
BOLTON TOWN OF	222 BOLTON CENTER RD	BOLTON, CT 06043
SPOSITO DAVID	55 HEBRON RD	BOLTON, CT 06043
COTNOIR RICHARD DOUGLAS	41 HEBRON RD	BOLTON, CT 06043
ALLEMAN RONALD E & BEVERLY S	21 HEBRON RD	BOLTON, CT 06043
PALUSO JOSEPH	27 RICHARDSON DR	HEBRON, CT 06248
BOLTON TOWN OF	29 HEBRON RD	BOLTON, CT 06043
MINICUCCI CHARLES J EST & HEBRON COUNTRY	C/O THOMAS FIORENTINO 773 MAIN ST	MANCHESTER, CT 06040
PRUITT JOSHUA S & THERIAULT AMANDA	46 CLARK RD	BOLTON, CT 06043
BOLTON TOWN OF	222 BOLTON CENTER RD	BOLTON, CT 06043
MASSEY JAMES W	254 US ROUTE 6W	ANDOVER, CT 06232
TOOMEY JOHN B JR & DWIRE JAMES L	45 HEBRON RD	BOLTON, CT 06043
DAVIS SHANE C	39 HEBRON RD	BOLTON, CT 06043
JENNINGS BRIAN K & EILEEN DULEN-	25 HEBRON RD	BOLTON, CT 06043
WRAIGHT MATTHEW &	17 HEBRON RD	BOLTON, CT 06043
HOLLINGSWORTH PATRICIA A	50 CLARK RD	BOLTON, CT 06043
BOLTON TOWN OF	222 BOLTON CENTER ROAD	BOLTON, CT 06043
SPINA PAMELA & SPINA WILLIAM ANTHONY	43 HEBRON RD	BOLTON, CT 06043
BOLTON TOWN OF	222 BOLTON CENTER RD	BOLTON, CT 06043
PALUSO JOSEPH	27 RICHARDSON DR	HEBRON, CT 06248

Town of Bolton, CT

October 24, 2025

IW-25-17

**Inland Wetlands** 

Status: Active

Submitted On: 10/23/2025

### **Primary Location**

206 BOLTON CENTER RD BOLTON, CT 06043

### Owner

No owner information

### **Applicant**

Wade Thomas

**J** 860-526-9591 ext. 233

@ wthomas@nlja.com

n P.O. Box 337

86 Main Street Chester, CT 06412

Internal Use	
<b>△</b> Conditions	
■ Petition Received?	□ Date Received
_	_
■ Date of Newspaper Publication of Inland/Wetlands Commission Action	
_	
■ Bond Required?	
_	

### Parcels Included in Project

MBL / Parcel ID	
Parcel ID 1970	
MBL / Parcel ID	
Parcel ID 881	
MBL / Parcel ID	
Parcel ID 147	
MBL / Parcel ID	
Parcel ID 160	
Additional Applicant Info	
Additional Applicant into	
Applicant Type*	
Owner	
Permit Info	
Type of Application*	Permit For*
New Application	Application by Town of Bolton or Non- profit group
	From Broak

Occupancy Type* Lots Town of Bolton Work Description* ② Construct a Town Center Subsurface Sewage Disposal System serving 206 Bolton Center Road (Bentley Library), 220 Bolton Center Road (Police Building), 222 Bolton Center Road (Town Hall) and 266 Bolton Center Road (Rose Farm). **Development Title** Town of Bolton Town Center Subsurface Sewage Disposal System **△** Comments Distance from Inland Wetlands and Watercourses: **Current Distance Proposed Distance** 80 90 Wetland / Watercourses Project Information

Size of Subject Property (acres)	Total area of wetlands to be affected by the activity
123.96	(acres)
	0.165

Described how the proposed activity affects wetlands, watercourses, and the regulated areas.

Temporary disturbance for installation of sanitary sewers, sanitary manholes, a community leaching system and upgradient leaching system curtain drain.

Described measures that will be taken to minimize the impact on wetlands, watercourses, and the regulated areas.

Low Permeability Seepage Barriers will be installed in intervals in the pipe trench to prevent, or significantly reduce, dewatering of the inland wetlands. Disturbed areas will be restored with appropriate wetland and upland seed mixes from New England Wetland Plants, Inc. Temporary biodegradable erosion control blankets will be used on all slopes exceeding 5H:1V to minimze erosion during revegetation.

Is there a Conservation or Preservation Restruction on the Property?

Is this an activity associated with a use for which you intend to apply to the Planning & Zoning Commission?

Yes

Yes

Please read and check the following statements. By checking these boxes, you agree to abide by the statutes and ordinances of the Town of Bolton and the State of Connecticut.

I understand that the Commission may require additional information at any time during the review of the application as described in Section 7.6 of the Inland Wetlands and Watercourses Regulations.*



The Applicant must ensure that this application is complete and conforms with the Inland Wetlands and Watercourses Regulations (available at the Land Use Office for \$10.00). Ten (10) copies of supporting documents must be provided. The Commission encourages the applicant to discuss any project with the Town Staff and/or the Commission before submitting an application. The Commission requests that applications be submitted at least one week before the meeting.*



The Agency shall monitor all Bolton wetland and watercourses and have enforcement powers as described in Section 14 of the Inland Wetlands and Watercourses Regulations. The Commission Members and designed agent(s) may make regular inspections upon reasonable notice of all regulated activities to investigate possible violations of the Inland Wetlands and Watercourses Regulations.*

If this application is filed with the Inland Wetlands
Agent under Section 12.1 of the Inland Wetlands and
Watercourses Regulations, the Applicant may appeal
the Agent's decision according to the process
descibed in section 12.2 of the Inland Wetlands and
Watercourses Regulations. *





### Attorney Info

Name	Address
City	State
Zip	Phone
<b></b>	
Forest!	
Email	

### **Engineer Information**

Company Name	Engineer Name
Address	Oit.
Address	City
State	Zip
Phone	Registration #
Insurance Expiration	AOR
_	
Email	

### **Experts Retained by Applicant**

Name	Title / Expertise
Richard R. Snarski	Certified Professional Soil Scientist
Address	City
30 Gina Lane	Marlborough
State	Zip Code
Connecticut	06447

Phone No Email

860.918.1970 richsnarski@gmail.com

Name Title / Expertise

Matt Davison PSS, PWS, CPESC, CESSWI, CT

Forester

Address City

10 Maple Street Chester

State Zip Code

Connecticut 06412

Phone No Email

860.803.0938 matt@davisonenvironmental.com

### Additional Project Info

_ _

Total Acreage Distance to Town Line


123.96

<b>≜</b> Extende	led	ng Not Required
Attach	hments	
B	List of Names and Addresses of Abuttin Adjacent Properties.pdf	ng Property Owners
	Uploaded by Danielle Palazzini on Oct 24, 2025 at 8:09 AM	
	Key Map of Property	
	Key Map of Properties.pdf	
	Uploaded by Wade Thomas on Oct 23, 2025 at 3	:08 PM
	Combined 09630053.pdf	
	Combined 09630053.pdf	
	Uploaded by Wade Thomas on Oct 23, 2025 at 2	:58 PM

# ArcGIS Web Map



ABBREVIATIONS				
	Bit.	BITUMINOUS		
	B.O.S.	BOTTOM OF STONE		
	C#	ALIGNMENT CURVE NUMBER		
	Conc.	CONCRETE		
	CL&P	CONNECTICUT LIGHT AND POWER		
	CPEP	CORRUGATED POLYETHYLENE PIPE		
	EL.	ELEVATION		
	H.P.	HIGH POINT		
	INV.	INVERT		
	L#	ALIGNMENT LINE NUMBER		
	N/F	NOW OR FORMERLY		
	PERF.	PERFORATED		
	RCP	REINFORCED CONCRETE PIPE		
	STA.	STATION		
	SNET	SOUTHERN NEW ENGLAND TELEPHONE CO.		
	T.O.P.	TOP OF PIPE		
	T.O.W.	TOP OF WALL		
	TYP.	TYPICAL		



**PERMITTING JULY 2025** 

PROGRESS PRINT

DO NOT USE FOR CONSTRUCTION

☐ FOR PRELIMINARY REVIEW

☐ FOR INFORMATION ONLY

DATE ISSUED October 23, 2025 NATHAN L. JACOBSON & ASSOCIATES

☐ FOR FINAL REVIEW

### TOWN OF BOLTON CONNECTICUT

### TOWN CENTER SUBSURFACE SEWAGE DISPOSAL SYSTEM

### **BOARD OF SELECTMEN**

RODNEY FOURNIER, FIRST SELECTMAN PAMELA SAWYER, SELECTMAN TIMOTHY SADLER, SELECTMAN ROBERT MORRA, SELECTMAN MATHER CLARKE, SELECTMAN AMANDA GORDON, SELECTMAN GWEN MARRION, SELECTMAN

DIRECTOR OF COMMUNITY DEVELOPMENT


PATRICE CARSON, A.I.C.P.

TOWN ADMINISTRATOR JAMES RUPERT

LANCE DIMOCK


ROAD FOREMAN


SCHEDULE OF DRAWINGS				
SHEET No.	TITLE			
1 OF 13	COVER SHEET			
2 OF 13	TOPOGRAPHIC SURVEY AND INDEX PLAN			
3 OF 13	SITE PLAN - OVERALL LAYOUT			
4 OF 13	SITE, GRADING AND UTILITY PLAN LIBRARY SITE			
5 OF 13	SITE, GRADING AND UTILITY PLAN			
6 OF 13	SITE, GRADING AND UTILITY PLAN TOWN HALL SITE			
7 OF 13	SITE, GRADING AND UTILITY PLAN			
8 OF 13	SITE, GRADING AND UTILITY PLAN ROSE FARM PROPERTY LEACHING SYSTEM			
9 OF 13	EROSION AND SEDIMENTATION CONTROL NOTES AND DETAILS			
10 OF 13	PROJECT NOTES AND SOIL INFORMATION			
11 OF 13	DETAILS			
12 OF 13	DETAILS			
13 OF 13	DETAILS			
4012	the observation of the state of			
511	BM 1/2 00 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			























THE SUBJECT PROJECT INCLUDES THE CONSTRUCTION OF A SUBSURFACE WASTEWATER DISPOSAL SYSTEM, SEPTIC TANKS AND

IT IS PROPOSED TO PERFORM CONSTRUCTION IN THE SPRING 2026. IN GENERAL, THE SEQUENCE FOR CONSTRUCTION AND SITE

- 8. REMOVE REMAINING SEDIMENT AND EROSION CONTROL MEASURES ONCE VEGETATION HAS BECOME ESTABLISHED

THE CONTRACTOR SELECTED TO CONSTRUCT THIS PROJECT WILL BE RESPONSIBLE FOR IMPLEMENTATION OF SEDIMENT AND EROSION CONTROL MEASURES ON THIS SITE. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR WILL PROVIDE THE BOLTON INLAND WETLANDS ENFORCEMENT OFFICER WITH THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE RESPONSIBLE

A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE THE OWNER'S AGENT WITH THE NAMES AND TELEPHONE NUMBERS OF THE RESPONSIBLE PERSONS TO BE CONTACTED IN THE EVENT OF AN EROSION

THE CONTRACTOR SHALL AT ALL TIMES KEEP SUFFICIENT ADDITIONAL SEDIMENTATION CONTROL FENCE AND/OR HAY BALES ON THE PROJECT SITE TO CONTROL UNFORESEEN EROSION AND/OR SEDIMENT PROBLEMS. IN THE EVENT OF A PROBLEM THE CONTRACTOR SHALL PROMPTLY STABILIZE THE PROBLEM AND CONTAIN ANY SEDIMENT AND THEN NOTIFY THE OWNER'S AGENT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF THE EROSION AND SEDIMENT CONTROL PLAN FOR THE

THE MINIMUM STANDARDS FOR ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE THOSE OUTLINED IN THE "202 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL", LATEST REVISION. ALTERNATIVE MEASURES, METHODS, MEANS AND TECHNIQUES MAY BE ALLOWED WITH THE PRIOR APPROVAL OF THE OWNER'S AGENT.

- NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE WITHIN AREAS DESIGNATED AS INLAND WETLANDS, WATERCOURSES OR FLOODPLAINS, DESIGNATED UPLAND REVIEW ZONES OR WITHIN STREAM CHANNEL ENCROACHMENT LINES WITHOUT ALL
- TEMPORARY EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION.
- ALL EROSION AND SEDIMENT CONTROLS SHALL BE MAINTAINED CONTINUOUSLY AND SHALL NOT BE REMOVED UNTIL ALL
- THE CONTRACTOR SHALL LIMIT THE DISTURBANCE OF LAND TO THOSE AREAS SHOWN ON THE DRAWINGS AND SHALL TAKE
- WHERE PRACTICABLE, THE CONTRACTOR SHALL PLAN HIS CONSTRUCTION OPERATIONS SO AS TO LIMIT THE AREAS OF EXPOSED SOIL TO AREAS ACTIVELY UNDER CONSTRUCTION. THE CONTRACTOR SHALL TAKE REASONABLE CARE TO LIMIT
- THE PERIOD OF EXPOSURE OF DISTURBED AREAS. THE INSTALLATION OF PERMANENT VEGETATIVE MEASURES SHALL BE
- ADEQUATE PROVISIONS SHALL BE TAKEN TO PROTECT ALL EXPOSED CUT AND FILL SLOPES FROM SURFACE WATER FLOW
- . ALL MATERIAL FROM CLEARING AND GRUBBING OPERATIONS SHALL BE DISPOSED OF IN A LAWFUL MANNER.
- WATER FROM DEWATERING OPERATIONS SHALL NOT BE DISCHARGED DIRECTLY TO ANY WETLAND OR WATERCOURSE. SUCH WATER SHALL BE DISCHARGED TO AN APPROVED SEDIMENT BASIN AND/OR FILTER DEVICE OR TO A STORM DRAINAGE SYSTEM ONLY WHEN APPROVED. NO WATER FROM DEWATERING OPERATIONS SHALL BE DISCHARGED INTO A SANITARY
- 9 THE STORAGE WASHING FUELING AND MAINTENANCE OF FOLIPMENT AND VEHICLES SHALL TAKE PLACE IN DESIGNATED AREAS ONLY. IN THE EVENT OF A CONTAMINANT SPILL THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION OIL AND CHEMICAL SPILL RESPONSE DIVISION (860-424-3338) AND THE OWNER'S

SITE INVESTIGATIONS SHALL BE MADE TO DETERMINE IF THERE IS A SUFFICIENT QUANTITY OF TOPSOIL OF GOOD QUALITY ON THE SITE TO JUSTIFY STRIPPING. HIGH QUALITY TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOAM, SANDY CLAY LOAM, CLAY LOAM). OTHER SOIL TYPES WITH HIGH ORGANIC CONTENT MAY BE FOUND SUITABLE AFTER FESTING. IT SHALL BE FREE OF DEBRIS. TRASH. STUMPS. ROCKS. ROOTS AND NOXIOUS WEEDS. IT SHALL GIVE EVIDENCE

ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY TO DETERMINE THE PROPER APPLICATION RATES OF LIME

- STRIPPING OF TOPSOIL SHALL BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. THE DEPTH OF REMOVAL MAY WARY DEPENDING ON THE SITE CONDITIONS. ALL SEDIMENT CONTROLS SHALL BE IN PLACE PRIOR TO BEGINNING STRIPPING
- TOPSOIL SHALL BE STOCKPILED IN SUCH A MANNER THAT NATURAL SURFACE WATER FLOW IS NOT OBSTRUCTED AND NO
- SIDE SLOPES OF STOCKPILES SHALL NOT BE STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.
- TEMPORARY SEEDING OF STOCKPILES SHALL BE COMPLETED WITHIN 30 DAYS OF THE FORMATION OF THE STOCKPILE, IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE COVER REQUIREMENTS.
- 6. PREVIOUSLY ESTABLISHED GRADES ON THE AREAS TO BE TOPSOILED SHALL BE MAINTAINED ACCORDING TO THE
- WHERE THE pH OF THE SUBSOIL IS 6.0 OR LESS, GROUND AGRICULTURAL LIMESTONE SHALL BE SPREAD IN ACCORDANCE
- WITH THE SOIL TEST TO A pH OF 6.0 TO 6.5 OR THE VEGETATIVE ESTABLISHMENT PRACTICE BEING USED.
- TOPSOIL SHALL NOT BE PLACED WHILE IN A FROZEN OR MUDDY CONDITION. WHEN THE SUBGRADE IS EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING OR PROPOSED SODDING OR SEEDING. THE
- ANY IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOILING OR OTHER OPERATIONS SHALL BE CORRECTED IN ORDER TO PREVENT THE FORMATION OF DEPRESSIONS OR WATER POCKETS. TOPSOIL SHALL BE COMPACTED ENOUGH TO ENSURE GOOD CONTACT WITH THE UNDERLYING SOIL AND TO OBTAIN A
- UNIFORM FIRM SEEDBED FOR THE ESTABLISHMENT OF A DURABLE TURF. UNDUE COMPACTION IS TO BE AVOIDED AS IT INCREASES RUNOFF VELOCITY AND VOLUME, AND PREVENTS SEED GERMINATION.
- IMMEDIATELY FOLLOWING TOPSOIL APPLICATION, PROTECT THE TOPSOIL FROM EROSION BY EITHER SODDING, SEEDING
- ALL GRADED OR DISTURBED AREAS INCLUDING SLOPES SHALL BE PROTECTED DURING CLEARING AND CONSTRUCTION IN
- AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS OR
- 3. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER
- FILL MATERIAL SHALL BE FREE OF BRUSH, RUBBISH, ROCKS, LOGS, STUMPS, BUILDING DEBRIS AND OTHER OBJECTIONABLE

- TOPSOILING SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE REQUIREMENTS FOR TOPSOILING.
- THE EXPOSED SOIL SURFACE SHALL BE MOISTENED PERIODICALLY WITH ADEQUATE QUANTITIES OF WATER TO CONTROL
- COVER SURFACE WITH CRUSHED STONE OR COARSE GRAVEL. IN AREAS ADJACENT TO WATERWAYS USE CHEMICALLY STABLE AGGREGATE.
  - MAINTENANCE WHEN TEMPORARY DUST CONTROL MEASURES ARE USED, REPETITIVE TREATMENT SHALL BE APPLIED AS NEEDED TO ACCOMPLISH CONTROL.

### VEGETATIVE SOIL COVER

### TEMPORARY SEEDING

### INSTALLATION REQUIREMENTS

- SITE PREPARATION
- GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION AND MULCH ANCHORING. ALL GRADING SHOULD BE DONE IN ACCORDANCE WITH THE REQUIREMENTS FOR
- INSTALL NEEDED EROSION CONTROL MEASURES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, SEDIMENT BASINS AND GRASSED WATERWAYS.

### SEEDBED PREPARATION

APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS SUCH AS THOSE OFFERED BY THE UNIVERSITY OF CONNECTICUT SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVE EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE IMING IS CRITICAL. FERTILIZER MAY BE APPLIED AT THE RATE OF 300 POUNDS PER ACRE OR 7.5 POUNDS PER 1.000 SQUARE FEET OF 10-10-10 OR EQUIVALENT. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AS

TONS/ACRE LBS/1,000 SQUARE FEET SOIL TEXTURE CLAY, CLAY LOAM, AND HIGH ORGANIC SOIL SANDY LOAM, LOAM, SILT LOAM LOAMY SAND, SAND

### REFER TO COUNTY SOIL SURVEY REPORT FOR SOIL TEXTURES AT THE SITE

- ANNUAL RYE GRASS 40 LBS/ACRE, 1 LB/1000 SF
- WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER LIME AND SEED
- 3. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDEF HYDROSEEDINGS WHICH INCLUDE MULCH, MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED BY 10
- SPRING SEEDINGS USUALLY GIVE THE BEST RESULTS, SPRING SEEDINGS OF ALL SEED LEGUMES IS RECOMMENDED.
   HOWEVER, LATE SUMMER SEEDINGS PRIOR TO SEPTEMBER 1 CAN BE MADE. WHEN CROWN VETCH IS SEEDED IN LATE SUMMER AT LEAST 35 PERCENT OF THE SEED SHOULD BE HARD SEED (UNSCARIFIED), THE RECOMMENDED SEEDING DATES
  - MARCH 15 THROUGH JUNE 15 AUGUST 15 THROUGH OCTOBER 15

### PERMANENT SEEDING

### INSTALLATION REQUIREMENTS

SEEDBED PREPARATION

GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION EEDING, MULCH APPLICATION AND ANCHORING, AND MAINTENANCE. ALL GRADING SHOULD BE BE DONE IN ACCORDANCE WITH THE REQUIREMENTS FOR LAND GRADING.

APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TESTS SUCH AS THOSE OFFERED BY THE UNIVERSITY OF CONNECTICUT SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVI EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES. OR WHERE TIMING I RITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 300 POUNDS PER ACRE OR 7.5 POUNDS PER 1,000 SQUARE FEE USING 10-10-10 OR EQUIVALENT. IN ADDITION, 300 POUNDS OF 38-0-0 PER ACRE OR EQUIVALENT OF SLOW RELEASE NITROGEN MAY BE USED FOR TOPDRESSING. APPLY GROUND LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AS FOLLOWS:

SOIL TEXTURE	TONS/ACRE	LBS/1,000 SQUARE FEET
CLAY, CLAY LOAM, AND HIGH ORGANIC SOIL	3	135
SANDY LOAM, LOAM, SILT LOAM	2	90
LOAMY SAND SAND	1	45

- REFER TO COUNTY SOIL SURVEY REPORT FOR SOIL TEXTURES AT THE SITE. 2. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OR DISCING OPERATION SHALL BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FINE SEEDBED IS PREPARED. ALL BUT CLAY OR SILTY SOILS
- AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE. 3. REMOVE FROM THE SURFACE ALL STONES ONE INCH OR LARGER IN ANY DIMENSION UNLESS OTHERWISE SPECIFIED REMOVE ALL OTHER DEBRIS SUCH AS WIRE, CABLE, TREE ROOTS, PIECES OF CONCRETE, CLODS, LUMPS OR OTHER
- INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED, THE AREA MUST BE RETILLED AND
- FIRMED AS ABOVE. SEEDING DATES
- SPRING SEEDINGS USUALLY GIVE THE BEST RESULTS. SPRING SEEDINGS OF ALL SEED MIXES WITH LEGUMES IS RECOMMENDED, HOWEVER LATE SUMMER SEEDINGS PRIOR TO SEPTEMBER 15 CAN BE MADE. WHEN CROWN VETCH IS SEEDED IN LATE SUMMER AT LEAST 35 PERCENT OF THE SEED SHOULD BE HARD SEED (UNSCARIFIED). THE RECOMMENDED
- SEPTEMBER 1 THROUGH OCTOBER 15

WITH THE EXCEPTION OF CROWN VETCH, THE FINAL SEEDING DATE MAY BE EXTENDED 15 DAYS IN THE COASTAL TOWNS OF NEW LONDON, MIDDLESEX, NEW HAVEN AND FAIRFIELD COUNTIES

- NEW ENGLAND WILDFLOWER SEED MIX AT 23 LBS. / ACRE. NEW ENGLAND WETLANDS PLANTS, INC.
- APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER, NORMAL
- WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED. THE SEEDBED SHOULD BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG. SEEDING OPERATIONS SHOULD BE
- 4. FROST CRACK SEEDING MUST BE DONE IN LATE WINTER OR EARLY SPRING. SUITABLE WEATHER CONDITIONS ARE FREEZING NIGHTS AND THAWING DAYS WITH LITTLE OR NO SNOW COVER. SEEDING RATES MUST BE INCREASED 10 PERCENT. WHEN
- HYDRAULIC APPLICATION (HYDROSEEDING), IS A SUITABLE METHOD FOR USE ON CRITICAL AREAS. WHEN HYDROSEEDING, A SEEDBED IS PREPARED IN THE CONVENTIONAL WAY OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND TO REMOVE SURFACE STONES LARGER THAN ONE INCH IN DIAMETER. SLOPES MUST BE NO STEEPER THAN 2 TO 1 (2 FEE HORIZONTALLY TO ONE FOOT VERTICALLY). LIME AND FERTILIZER MAY BE APPLIED SIMULTANFOLISLY WITH THE SEED. THE USE OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). FIBER MULCH DOES NOT PROVIDE ADEQUATE SEEDBED PROTECTION. BETTER PROTECTION IS GAINED BY USING STRAW MULCH AND HOLDING IT WITH ADHESIVE MATERIALS OR 500 POUNDS PER ACRE OF WOOD FIBER MULCH. SEEDING RATES MUST BE
- INCREASED BY 10 PERCENT WHEN HYDROSEEDING 6. APPLY MULCH ACCORDING TO THE TEMPORARY MULCHING MEASURE.
- 7. IF SEEDING CANNOT BE DONE WITHIN THE SEEDING DATES, USE THE TEMPORARY MULCHING MEASURE TO PROTECT THE SITE AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD MAINTENANCE
- 1. LIME ACCORDING TO A SOIL TEST OR AT A MINIMUM OF EVERY FIVE YEARS USING A RATE OF TWO TONS PER ACRE (100
- WHERE GRASSES PREDOMINATE, FERTILIZE ACCORDING TO A SOIL TEST OR BROADCAST BIENNIALLY, 300 POUNDS OF 10-10-10 OR EQUIVALENT PER ACRE (7.5 POUNDS PER 1,000 SQUARE FEET).
- 3. WHERE LEGUMES PREDOMINATE, FERTILIZE ACCORDING TO A SOIL TEST OR BROADCAST EVERY THREE YEARS 300 POUNDS OF 0-20-20 PER ACRE OR EQUIVALENT (7.5 POUNDS PER 1.000 SQUARE FEET)

### NON-LIVING SOIL PROTECTION

### MULCH FOR SEED MATERIALS

 SELECT MULCH MATERIALS BASED ON SITE CONDITIONS, AVAILABILITY OF MATERIALS AND LABOR AND EQUIPMENT. OTHER
MATERIALS MAY BE USED ONLY WITH THE PERMISSION OF THE APPROVING AUTHORITY. INSTALLATION REQUIREMENTS

ORGANIC MULCHES

1. ORGANIC MULCHES MAY BE USED IN ANY AREA WHERE MULCH IS REQUIRED, SUBJECT TO THE RESTRICTIONS NOTED BELOW

	RATES	
MULCHES	PER ACRE	PER 1,000 SQUARE FEET
STRAW	1 1/2 - 2 TONS	35-45 LBS

### APPLICATION

MULCH MATERIALS SHALL BE SPREAD UNIFORMLY. BY HAND OR MACHINE. WHEN SPREADING STRAW OR HAY MULCH BY HAND, DIVIDE THE AREA TO BE MULCHED INTO APPROXIMATELY 1,000 SQUARE FOOT SECTIONS AND PLACE 35-45 POUNDS (1 BALE) OF STRAW OR HAY IN EACH SECTION TO ENSURE UNIFORM DISTRIBUTION.

HAY OR STRAW MULCHES MUST BE ANCHORED IMMEDIATELY AFTER APPLICATION TO PREVENT WINDBLOWING. HAY OR

MAINTENANCE ALL MULCHES MUST BE INSPECTED PERIODICALLY, IN PARTICULAR AFTER RAINSTORMS, TO CHECK FOR RILL EROSION. WHERE EROSION IS OBSERVED, ADDITIONAL MULCH SHOULD BE APPLIED. NETS SHALL BE INSPECTED AFTER RAINSTORMS FOR DISLOCATION OR FAILURE. IF WASHOUTS OR BREAKAGE OCCUR, REINSTALL NET AS NECESSARY AFTER REPAIRING DAMAGE TO THE SLOPE. INSPECTIONS SHALL TAKE PLACE UNTIL GRASSES ARE FIRMLY ESTABLISHED. GRASSES SHALL NOT BE CONSIDERED ESTABLISHED UNTIL A GROUND COVER IS ACHIEVED WHICH IS MATURE ENOUGH TO CONTROL SOIL EROSION AND TO SURVIVE SEVERE WEATHER CONDITIONS. WHERE MULCH IS USED IN CONJUNCTION WITH ORNAMENTAL PLANTINGS, INSPECT PERIODICALLY THROUGHOUT THE YEAR TO DETERMINE IF MULCH IS MAINTAINING COVERAGE OF THE

### SEDIMENT IMPOUNDMENTS, BARRIERS, AND FILTERS

### HAY BALE BARRIER

### INSTALLATION REQUIREMENTS

CHANNEL FLOW APPLICATIONS

FOLLOWING ADDITION

- SHEET FLOW APPLICATIONS BALES SHALL BE PLACED IN A SINGLE ROW, LENGTHWISE ON THE CONTOUR, WITH THE ENDS OF ADJACENT BALES TIGHTLY
- 2. ALL BALES SHALL BE EITHER WIRE-BOUND OR STRING TIED. BALES SHALL BE INSTALLED SO THAT BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES TO PREVENT DETERIORATION OF THE

3. A TRENCH SHALL BE EXCAVATED THE WIDTH OF A BALE AND THE LENGTH OF THE PROPOSED BARRIER TO A MINIMUM DEPTH OF 4 INCHES. AFTER THE BALES ARE STAKED AND CHINKED, THE EXCAVATED SOIL SHALL BE BACKFILLED AGAINST THE

- BARRIER. BACKFILL SOIL SHALL CONFORM TO THE GROUND LEVEL ON THE DOWNHILL SIDE AND SHALL BE BUILT UP TO 4 NCHES AGAINST THE UPHILL SIDE OF THE BARRIER. BALES SHOULD BE PLACED 10 FEET AWAY FROM THE TOE OF SLOPES LINI ESS OTHERWISE SHOWN ON THE DRAWINGS OR DIRECTED 4. EACH BALE SHALL BE SECURELY ANCHORED BY AT LEAST TWO STAKES DRIVEN THROUGH THE BALE. THE FIRST STAKE IN
- EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE TO FORCE THE BALES TOGETHER. STAKES SHALL BE DRIVEN DEEP ENOUGH INTO THE GROUND TO SECURELY ANCHOR THE BALES. 5. THE GAPS BETWEEN BALES SHALL BE CHINKED (FILLED BY WEDGING) STRAW BETWEEN THEM TO PREVENT WATER FROM FLOWING BETWEEN THE BALES.
- BALES SHALL BE PLACED IN A SINGLE ROW, LENGTHWISE, ORIENTED PERPENDICULAR TO THE CONTOUR, WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER

2. THE REMAINING STEPS FOR INSTALLING A BALE BARRIER FOR SHEET FLOW APPLICATIONS APPLY HERE, WITH THE

- 3. THE BARRIER SHALL BE EXTENDED TO SUCH A LENGTH THAT THE BOTTOMS OF THE END BALES ARE HIGHER IN ELEVATION THAN THE TOP OF THE LOWEST MIDDLE BALE TO ASSURE THAT SEDIMENT LADEN RUNOFF WILL FLOW EITHER THROUGH OR OVER THE BARRIER BUT NOT AROUND IT
- INSPECTION SHALL BE MADE AFTER EACH STORM EVENT AND PERIODICALLY DURING PROLONGED RAIN EVENTS AND REPAIR
- 2. ACCUMULATED SEDIMENT BEHIND THE BALES SHALL BE REMOVED WHEN IT REACHES 1/2 OF THE ORIGINAL HEIGHT OF THE

### GEOTEXTILE SILT FENCE

### MATERIALS


1 GEOTEXTILE GEOTEXTILE SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON, POLYESTER OR ETHYLENE FILAMENTS AND


PHYSICAL PROPERTY **REQUIREMENTS** FILTERING EFFICIENCY 75% (MIN) TENSILE STRENGTH AT 20% (MAX) ELONGATION EXTRA STRENGTH 50 LBS./LIN. IN. (MIN) 30 LBS./LIN. IN. (MIN)

- FLOW RATE 12 GAL./SF/MIN. (MIN.) STAKES FOR GEOTEXTILE SILT FENCES SHALL BE 1" x 1" WOOD WITH A MINIMUM LENGTH OF 5 FEET.
- 3. WIRE FENCE REINFORCEMENT FOR GEOTEXTILE SILT FENCES USING STANDARD STRENGTH MATERIAL SHALL BE A MINIMUM OF 42 INCHES IN HEIGHT, A MINIMUM OF 14 GAUGE AND SHALL HAVE A MAXIMUM MESH SPACING OF 6 INCHES INSTALLATION REQUIREMENTS
- THE HEIGHT OF THE BARRIER SHALL NOT EXCEED 36 INCHES. (HIGHER BARRIERS MAY IMPOUND VOLUMES OF WATER SUFFICIENT TO CAUSE FAILURE OF THE STRUCTURE). THE SEDIMENTATION CONTROL FENCE SHALL BE PLACED 10 FEET AWAY FROM THE TOE OF SLOPES UNLESS OTHERWISE SHOWN ON THE DRAWINGS OR DIRECTED.
- WHEN JOINTS ARE NECESSARY, GEOTEXTILE ROLL ENDS SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6" OVERLAP AND SECURELY SEALED IN CONFORMANCE WITH THE MANUFACTURERS RECOMMENDATIONS
- 3. POSTS SHALL BE SPACED A MAXIMUM OF 10 FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM DEPTH OF 12 4. WHEN STANDARD STRENGTH GEOTEXTILE IS USED, A WIRE MESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE
- UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST 1 INCH LONG, TIE WIRES OR HOG RINGS. TH WIRE SHALL EXTEND INTO A TRENCH A MINIMUM OF 2 INCHES AND SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE 5. THE STANDARD STRENGTH GEOTEXTILE SHALL BE STAPLED, WIRED OR TIED TO THE WIRE FENCE, AND 8 INCHES OF THE
- GEOTEXTILE SHALL BE EXTENDED INTO THE TRENCH. 6. WHEN EXTRA STRENGTH GEOTEXTILE OR BURLAP AND CLOSER POST SPACING ARE USED, THE WIRE MESH SUPPORT FENCE
- MAY BE ELIMINATED 7. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE GEOTEXTILE.

REPLACEMENT SHALL BE MADE AS REQUIRED.

- 1. INSPECTION SHALL BE MADE AFTER EACH STORM EVENT AND PERIODICALLY DURING PROLONGED RAINFALL. REPAIR OR
- ACCUMULATED SEDIMENT BEHIND THE FENCE SHALL BE REMOVED WHEN IT REACHES 1/2 OF THE HEIGHT OF THE BARRIEF





STATE OF CT. DEPT. OF TRANSPORTATION, STANDARD

INCIDENTAL CONSTRUCTION, FORM 817, 2016, AS

AMENDED TO DATE.

SPECIFICATIONS FOR ROADS, BRIDGES, FACILITIES AND

SEE SHEET 10 FOR PROJECT NOTES.

DO NOT USE FOR CONSTRUCTION

PROGRESS PRINT

- ☐ FOR PRELIMINARY REVIEW
- ☐ FOR FINAL REVIEW ☐ FOR INFORMATION ONLY DATE ISSUED October 23, 2025

HIS DRAWING IS INTENDED TO BE USED FOR INFORMATION AND REVIEW

NATHAN L. JACOBSON & ASSOCIATES

URPOSES ONLY AND IS NOT INTENDED TO BE USED FOR CONSTRUCTION

TOWN OF BOLTON, CONNECTICUT

**TOWN CENTER SUBSURFACE** SEWAGE DISPOSAL

**EROSION AND** SEDIMENTATION CONTROL NOTES AND DETAILS

PERMITTING

ANY ALTERATIONS TO THIS DRAWING MADE WITHOUT THE EXPRESSE WRITTEN APPROVAL OF NATHAN L. JACOBSON & ASSOCIATES, INC. WILL B AT THE SOLE RISK OF THE PERSON OR FIRM MAKING SUCH UNAUTHORIZE ALTERATIONS AND NATHAN L. JACOBSON & ASSOCIATES, INC. WILL NEITHEF HAVE NOR ACCEPT ANY LIABILITY OR LEGAL EXPOSURE ARISING FROM SAI

UNAUTHORIZED ALTERATIONS.



Nathan L. Jacobson & Associates, Inc. 86 Main Street P.O. Box 337 Chester, Connecticut 06412-0337 Tel: (860) 526-9591 Fax: (860) 526-5416 www.nlja.com

NOT VALID WITHOUT ORIGINAL SEAL JOSEPH M. DILLON, P.E. CT REGISTRATION No. 22903

	7.22 1 (10111 0 1 1.20 2 1 1 1 2 2 2 1	
	REVISIONS	
No.	DESCRIPTION	DATE

© COPYRIGHT 2025 NATHAN L. JACOBSON & ASSOCIATES. INC.

ALL RIGHTS RESERVED.

DATE: JULY 2025 SHEET No .: SCALE: AS NOTED PROJECT No .: 09630053 CADD FILE: 09630053ED DESIGNED: BCC/JMD CEB DRAWN: CHECKED:

- 1. A PERMIT SHALL BE OBTAINED FROM THE LOCAL DEPARTMENT OF HEALTH (EASTERN HIGHLANDS HEALTH DISTRICT - EHHD) PRIOR TO INSTALLATION OF THE SUBSURFACE SEWAGE DISPOSAL SYSTEM. APPROVAL OF SYSTEM DESIGN BY THE CONNECTICUT DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION IS REQUIRED.
- 2. THE SUBSURFACE SEWAGE DISPOSAL SYSTEM SHALL BE CONSTRUCTED IN NFORMANCE WITH THE REQUIREMENTS OF THE CONNECTICUT PUBLIC HEALTH CODE AND TECHNICAL STANDARDS, SECTION 19-13-B103 OF THE REGULATIONS OF CONNECTICUT STATE AGENCIES, AS AMENDED, LOCAL DEPARTMENT OF HEALTH REGULATIONS AND TOWN ORDINANCES, AS APPLICABLE.
- 3. THE MINIMUM SEPARATING DISTANCE FROM A WATER SUPPLY WELL TO ANY PORTION OF THE SUBSURFACE SEWAGE DISPOSAL SYSTEM SHALL BE 75 FEET.
- 4. IF SOIL CONDITIONS ARE ENCOUNTERED AT DEPTHS SHALLOWER THAN SHOWN IN THE DEEP TEST HOLE LOGS (LEDGE, GROUNDWATER, MOTTLING), THE SANITARIAN AND DESIGN ENGINEER SHALL BE CONTACTED IMMEDIATELY AND CONSTRUCTION HALTED
- 5. NO DEVIATIONS FROM THE APPROVED DESIGN PLAN SHALL BE PERMITTED WITHOUT THE PRIOR WRITTEN APPROVAL OF THE LOCAL DEPARTMENT OF HEALTH AND THE DESIGN
- NO PORTION OF THE SUBSURFACE SEWAGE DISPOSAL SYSTEM SHALL BE BACKFILLED UNTIL MEASUREMENTS FOR RECORD DRAWINGS HAVE BEEN OBTAINED AND THE INSTALLATION HAS BEEN INSPECTED AND APPROVED BY THE TOWN SANITARIAN. THE LOCAL DEPARTMENT OF HEALTH (EASTERN HIGHLANDS HEALTH DISTRICT - EHHD) AND DESIGN ENGINEER SHALL BE NOTIFIED PRIOR TO THE FOLLOWING STAGES OF
  - STRIPPING OF TOPSOIL AND SCARIFYING BOTTOM OF EXCAVATED AREA

CONSTRUCTION (AS APPLICABLE) FOR INSPECTION PURPOSES:

- PLACEMENT OF LEACHING FILL MATERIAL PLACEMENT OF SEPTIC TANKS
- INSTALLATION OF THE LEACHING SYSTEM 7. THE SUBSURFACE SEWAGE DISPOSAL SYSTEM SHALL BE STAKED OUT BY A LICENSED
- LAND SURVEYOR AND THE SURVEYOR SHALL VERIFY THE DESIGN BENCHMARK PRIOR TO
- 8. THE CONTRACTOR SHALL RETAIN A LICENSED LAND SURVEYOR TO PREPARE RECORD DRAWINGS OF THE COMPLETED SUBSURFACE SEWAGE DISPOSAL SYSTEM, SHOWING INSTALLED LOCATIONS AND ELEVATIONS OF ALL SYSTEM COMPONENTS. RECORD DRAWINGS SHALL BE SUBMITTED TO THE LOCAL DEPARTMENT OF HEALTH AND DESIGN ENGINEER FOR REVIEW AND APPROVAL.
- 1. SEPTIC TANK PIPE AND FITTINGS SHALL BE SCHEDULE 40 PVC, ASTM 1785, WITH SOLVENT WELDED JOINTS, PIPE SIZE AS INDICATED ON THE DRAWINGS.
- SOLID WALL DISTRIBUTION PIPE AND FITTINGS SHALL BE FOUR (4) INCH DIAMETER SDR 35 PVC, ASTM 3034, WITH INTEGRAL RUBBER COMPRESSION GASKET JOINTS, ASTM D3212,
- 3. PIPE ADAPTERS PVC WITH GASKETED OR GLUED JOINTS FOR CONNECTING SCHEDULE
- 4. MAGNETIC TRACER TAPE POLYETHYLENE WITH METALLIC FOIL CORE, 2 INCHES WIDE, LABELED "SEWER - BURIED PIPELINE BELOW".
- THE SEPTIC TANKS SHALL CONFORM TO REQUIREMENTS OF THE PUBLIC HEALTH CODE AND ASTM C1277. TANKS SHALL CONTAIN TWO COMPARTMENTS, WITH 2/3 OF THE TOTAL CAPACITY PROVIDED IN THE FIRST COMPARTMENT. INLET AND OUTLET PIPING SHALL BE SEALED WITH A POLYETHYLENE GASKET CAST INTO THE PRECAST CONCRETE TANK WALL AND APPLICATION OF WATERPROOF NON-SHRINK MORTAR TO SEAL THE EXTERIOR PIPE ANNULUS. TANK SHALL BE H-20 LOAD CAPACITY. PROVIDE PRECAST CONCRETE TANK RISERS FOR ACCESS MANHOLES AND CAST IRON FRAMES AND COVERS AS INDICATED ON THE DRAWINGS.
- SEPTIC TANK OUTLET FILTERS SHALL BE ORENCO MODEL FT1254-36.
- DISTRIBUTION BOXES, RISERS AND LIDS POLYETHYLENE CONSTRUCTION AS MANUFACTURED BY TUF-TITE, OR APPROVED EQUAL. FLOW CONTROL FOR DISTRIBUTION BOX OUTLET PIPES TO BE PROVIDED BY POLYETHYLENE SPEED LEVELERS TO FIT SDR-35 PVC PIPE, AS MANUFACTURED BY TUF-TITE, OR APPROVED EQUAL. SIZE AND CONFIGURATION AS SHOWN ON THE DRAWINGS
- GEOTEXTILE MIRAFI 140N OR APPROVED EQUAL.
- SAND BEDDING FOR PIPES SHALL BE THOROUGHLY COMPACTED BELOW AND AROUND THE PIPE AND CONFORM TO THE FOLLOWING SPECIFICATIONS, UNLESS OTHERWISE APPROVED BY THE

### SQUARE MESH SIEVES

PERCENT PASSING BY WEIGHT 30% MAX.

10. WASHED CRUSHED STONE FOR LEACHING TRENCHES - STONE SHALL BE WASHED, CLEAN STONE OF HARD AND DURABLE NATURAL MATERIAL AND MEET THE FOLLOWING GRADATION LIMITS, UNLESS OTHERWISE APPROVED BY THE SANITARIAN AND DESIGN ENGINEER.

SQUARE MESH SIEVES PERCENT PASSING BY WEIGHT 90-100%

20-55% 0-10% 0-5% NO. 200

LEACHING FILL MATERIAL SHALL BE SAND OR SAND AND GRAVEL MIXTURES FREE OF STUMPS, TRASH, LUMPS OF CLAY, SOFT OR FLAKY MATERIAL OR ORGANIC MATTER, AND CONFORM TO THE FOLLOWING GRADATION LIMITS, UNLESS OTHERWISE APPROVED BY THE SANITARIAN AND DESIGN

### SQUARE MESH SIEVES

NO. 10

PERCENT PASSING BY WEIGHT

70-95%

15-60% 0-10%

NO. 40 NO. 100

NO. 200 0-3% FOLLOWING PLACEMENT AND COMPACTION, THE LEACHING FILL MATERIAL SHALL HAVE A PERCOLATION RATE BETWEEN 1 AND 10 MINUTES PER INCH.

- 12. COMMON EARTH FILL SUBSOIL, REUSED OR IMPORTED, FREE OF FROZEN CLUMPS OF SOIL. ANY MATERIALS CONTAINING VEGETABLE OR ORGANIC MATTER, SUCH AS MUCK, PEAT, ORGANIC SILT OR CLAY, TOPSOIL, SOD, TRASH, BRUSH, STUMPS, OR SOILS CONTAINING HIGH PLASTICITY CLAYS ARE NOT ACCEPTABLE. MAXIMUM STONE SIZE 3 1/2 INCHES
- 13. GRANULAR FILL Connecticut Department of Transportation FORM 816 Standard Specifications, Section M.02, Article M.02.01, Article M.02.06 Grading A Designation.
- 14. PROCESSED AGGREGATE Connecticut Department of Transportation REFERENCE FILE NO. 163-j, MEDIUM DESIGNATION, MARCH 4, 1963, REV. JUNE 26, 2001.
- 15. CRUSHED STONE CONFORM TO CTDOT FORM 818, SUBARTICLE M.01.01, SIZE AS INDICATED ON THE DRAWINGS.
- 16. TOPSOIL CONFORM TO CTDOT FORM 818, SUBARTICLE M.13.01; MAXIMUM STONE SIZE 1".
- 17. SEED MIXTURE TO BE AS FOLLOWS, OR APPROVED EQUAL:
- A. BLUEGRASS 10% CREEPING RED FESCUE 50%
- PERENNIAL RYE 30% D. ANNUAL RYE 10%
- APPLICATION RATE FOR NEW LAWN ESTABLISHMENT PER MANUFACTURER MINIMUM GERMINATION 85%

### CONSTRUCTION:

- THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION METHODS MEANS, TECHNIQUES, AND FOR CONSTRUCTION SITE SAFETY PRECAUTIONS. CONDUCT CONSTRUCTION OPERATIONS IN CONFORMANCE WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL SAFETY LAWS, RULES, REGULATIONS AND CODES.
- ALL EXCAVATIONS ARE TO BE PROPERLY SHORED AND BARRICADED TO PROTECT WORKERS, VEHICLES AND PEDESTRIANS DURING CONSTRUCTION.
- SEPTIC TANKS MUST BE SEALED WATERTIGHT. FOLLOWING INSTALLATION. CONDUCT LEAK TESTING PER ASTM C1277 VACUUM TEST OR WATER TEST BY PLUGGING INLET AND OUTLET PIPING AND FILL TANKS WITH WATER TO TOP OF TOP SLAB ELEVATION AND LET ET FOR 24 HOURS. LEAK TEST WILL PASS WITH NO WATER LEVEL DROP IN 1 HOUR FOLLOWING THE 24 HOUR PERIOD, THE TANKS SHALL BE INSPECTED BY THE SANITARIAN PRIOR TO BACKFILLING AND NO INFILTRATION OR EXFILTRATION SHALL BE EVIDENT. ALL VISUAL LEAKAGE AND INFILTRATION IN TANKS AND CHAMBERS SHALL BE LOCATED AND ELIMINATED. REPAIRS SHALL BE MADE IN A FIRST CLASS WORKMANLIKE MANNER. SET ALL TOP OF MANHOLE FRAME ELEVATIONS TO DRAIN SURFACE WATER AWAY FROM THE COVERS. DO NOT SET TANKS IN GROUNDWATER, PROVIDE DEWATERING AS MAY BE REQUIRED. BACKFILL TANKS WITH COMPACTED GRANULAR FILL.
- DURING CONSTRUCTION THE LEACHFIELD SYSTEM AREA SHALL BE PROTECTED FROM SURFACE WATER RUNOFF AT ALL TIMES BY THE USE OF APPROPRIATE BERMING AND/OR SWALES, ANY SILTATION OR SEDIMENTATION OF THE PREPARED SUBGRADE OR THE LEACHING SYSTEM DUE TO SURFACE WATER RUNOFF SHALL REQUIRE REMOVAL AND REINSTALLATION OF ALL AFFECTED PORTIONS OF THE SYSTEM AND IMPACTED SOIL AREAS AT THE SOLE EXPENSE OF THE CONTRACTOR.
- 5. NO UNAUTHORIZED VEHICLES SHALL BE PERMITTED ON, OR WITHIN FIFTY (50) FEET DOWNHILL OF THE PRIMARY AND RESERVE LEACHFIELD SYSTEM AREAS.
- LEACHING FILL MATERIAL SHALL BE SAMPLED AT THE SOURCE AND TESTED BY AN APPROVED COMMERCIAL TESTING LABORATORY FOR CONFORMITY TO THE GRADATION REQUIREMENTS SET FORTH HEREIN. AFTER ACCEPTANCE OF THE PROPOSED LEACHING FILL MATERIAL BASED ON SOURCE TESTING, THE FILL MATERIAL MAY BE DELIVERED TO THE PROJECT SITE BUT IS SUBJECT TO FURTHER TESTING AS DIRECTED BY THE AUTHORIZED INSPECTORS TO CONFIRM THE RESULTS OBTAINED FROM SAMPLING AND TESTING AT THE SOURCE. ANY LEACHING FILL MATERIAL FOUND TO BE NONCONFORMING WITH THE REQUIREMENTS SET FORTH HEREIN SHALL NOT BE USED FOR LEACHING FILL AND SHALL BE REMOVED FROM THE PROJECT SITE, UNLESS OTHERWISE PERMITTED BY THE AUTHORIZED INSPECTORS TO BE USED FOR OTHER COMMON EARTH FILLING OR
- REMOVE AND STOCKPILE TOPSOIL AND SUBSOIL FROM LEACHING SYSTEM AREA TO DIMENSIONS AND DEPTHS INDICATED ON THE DRAWINGS. USE ONLY TRACKED EXCAVATOR WORKING FROM THE LOWER TO THE UPPER EDGE OF THE LEACHFIELD SYSTEM AREA, LEAVING A SCARIFIED UNCOMPACTED SUBGRADE SURFACE. PLACE ALL LEACHING FILL FROM THE UPHILL EDGE OF THE LEACHFIELD SYSTEM AREA AND COMPACT IN 12 INCH LIFTS TO 85% OF MODIFIED PROCTOR DENSITY. PLACE LEACHING FILL TO TOP OF TRENCH ELEVATION.
- REMOVE ANY UNSUITABLE MATERIALS AS ORDERED BY THE AUTHORIZED INSPECTOR OR DESIGN ENGINEER AND REPLACE WITH LEACHING FILL MATERIAL. COMPACT IN 12" LIFTS
- FOLLOWING TRENCHING FOR LEACHING TRENCH INSTALLATION, LIGHTLY HAND RAKE ANY SMEARED SOIL SURFACES ON THE BOTTOM OR SIDE WALLS OF THE TRENCH PRIOR TO PLACEMENT OF WASHED CRUSHED STONE.
- 10. AFTER LEACHING TRENCH WASHED CRUSHED STONE, PIPING AND DISTRIBUTION BOXES FOR THE LEACHING SYSTEM HAVE BEEN INSTALLED, INSPECTED AND RECORD DRAWING SURVEY MEASUREMENTS OBTAINED, PLACE APPROVED NON-WOVEN GEOTEXTILE FABRIC OVER ALL CRUSHED STONE SURFACES. BACKFILL WITH GRANULAR FILL TO SUBGRADE IN PAVED AREAS. BACKFILL WITH COMMON EARTH TO FOUR (4) INCHES BELOW FINISHED GRADE IN NON-PAVED AREAS. APPLY 4 INCHES OF TOPSOIL TO ALL
- IN DRIVEWAY AREAS BACKFILL WITH GRANULAR FILL TO 8 INCHES BELOW FINAL GRADE.
   PLACE THE GRANULAR FILL IN 12 INCH MAXIMUM LIFTS COMPACTED TO 95% OF MODIFIED PROCTOR DENSITY. PROVIDE AN 8 INCH SURFACE COURSE OF PROCESSED AGGREGATE AND COMPACT TO 95% OF MODIFIED PROCTOR DENSITY
- 12. IN ALL NON-PAVED AREAS DISTURBED BY CONSTRUCTION, PLACE 4 INCHES OF TOPSOIL, FINE GRADE, REMOVE ALL STONES OVER 1" DIAMETER, FERTILIZE, LIME, SEED AND MULCH TO ESTABLISH A FULL PERENNIAL GRASS COVER. USE EROSION CONTROL BLANKET ON ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL.
- 13. REMOVE ALL STUMPS, STONES, EXCESS EXCAVATED MATERIAL AND CONSTRUCTION DEBRIS FROM THE SITE AND DISPOSE OFF SITE IN A LEGAL MANNER.

### EROSION AND SEDIMENT CONTROL:

- PRIOR TO CONSTRUCTION, THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE PERSON RESPONSIBLE FOR INSTALLATION AND MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROLS SHALL BE PROVIDED TO THE SANITARIAN AND TOWN ZONING OFFICIAL AND WETLANDS ENFORCEMENT OFFICER
- ALL CONSTRUCTION ACTIVITIES INVOLVING THE REMOVAL, DISTURBANCE OR DEPOSITION OF SOILS ARE TO BE PROVIDED WITH APPROPRIATE PROTECTIVE MEASURES TO MINIMIZE EROSION OF SOIL AND CONTAIN SEDIMENT DEPOSITION WITHIN THE AREA UNDER CONSTRUCTION (REFER TO 2024 CONNECTICUT GUIDELINES FOR SOIL EROSION AND
- 3. WHEREVER FEASIBLE, NATURAL VEGETATION SHALL BE RETAINED AND PROTECTED.
- ONLY THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME
- 5. PRIOR TO THE START OF CONSTRUCTION, TEMPORARY BALED HAY EROSION CHECKS, SEDIMENTATION FENCES CONSTRUCTION ENTRANCE AND OTHER APPROVED SEDIMEN CONTROL MEASURES SHALL BE INSTALLED WHERE SHOWN ON THE DRAWINGS AND AT OTHER LOCATIONS WHERE DEEMED NECESSARY BY THE AUTHORIZED INSPECTOR AND
- 6. WHEN LAND IS EXPOSED DURING CONSTRUCTION, THE PERIOD OF EXPOSURE SHALL BE KEPT TO A MINIMUM INSTALLING PERMANENT VEGETATION, PAVING, STRUCTURES, ETC AT THE EARLIEST POSSIBLE OPPORTUNITY. AREAS DISTURBED FOR GREATER THAN 1 MONTH SHALL BE PROVIDED WITH TEMPORARY SEEDING AND MULCH.
- ALL EROSION AND SEDIMENT CONTROLS SHALL REMAIN PLACE AND BE MAINTAINED REGULARLY IN PROPERLY FUNCTIONING CONDITION, UNTIL ALL AREAS EXPOSED DURING SITE CONSTRUCTION HAVE BEEN FULLY STABILIZED WITH VEGETATION.
- 8. AFTER THE SITE IS STABILIZED WITH A FULL GROWTH OF VEGETATION, REMOVE ALL EROSION AND SEDIMENT CONTROL MEASURES, SEED AND MULCH AREAS DISTURBED DURING SEDIMENT CONTROL MEASURE REMOVAL AND DISPOSE MATERIALS OFF SITE IN

### SUBSURFACE SEWAGE DISPOSAL SYSTEM - BASIS OF DESIGN

DESIGN FLOW NOT YET DETERMINED BUT WILL BE SITE LIMITED BASED ON WASTEWATER STRENGTH, MAXIMIZE SITE HYDRAULIC CAPACITY

### TOTAL DESIGN FLOW = GPD

REPLACE EXISTING SEPTIC TANK LOCATED EAST OF BUILDING NO. 73 WITH 2,500 GALLON TWO COMPARTMENT PRECAST CONCRETE H-20 LOAD CAPACITY SEPTIC TANK WITH EFFLUENT

REPLACE EXISTING SEPTIC TANK LOCATED AT DSN-002 WITH 2,500 GALLON TWO COMPARTMENT PRECAST CONCRETE H-20 LOAD CAPACITY SEPTIC TANK WITH EFFLUENT

TOTAL SEPTIC TANK CAPACITY = 2,500 + 2,500 = 5,000 GALLONS

LEACHFIELD SYSTEM SIZING EFFECTIVE LEACHING AREA (ELA) REQUIRED USING PERCOLATION RATE 10.1-20.0

USE 48 INCH WIDE X 12 INCH DEEP LEACHING TRENCHES, ELA = 3 SQ FT/LF, CC SPACING 8 FT USE 12 LEACHING TRENCHES 64 FT LONG EACH WITH DISTRIBUTION BOX IN THE CENTER OF TOTAL ELA PROVIDED = 768 FT X 3 SQ FT/FT = 2,304 SQ FT

PROVIDE 100% RESERVE AREA

RESERVE CAPACITY PROVIDED IN PRIMARY LEACHING SYSTEM FOR NON-PROBLEMATIC WASTEWATER, 2,400 GPD FOR PROBLEMATIC WASTEWATER, 1,610 GPD

CONFIGURATION - SET BOTTOM OF NEW LEACHING TRENCHES AT 6 INCHES BELOW EXISTING

PROVIDE FLOW SPLITTER DISTRIBUTION BOX TO LOAD THE EXISTING LEACHING TRENCHES AND NEW LEACHING TRENCHES EQUALLY AND PROVIDE HIGH LEVEL OVERFLOW FROM LOWEST EXISTING LEACHING TRENCH TO THE 3 NEW LEACHING TRENCHES. PROVIDE DEPTH OF PONDING MONITORING PIPES IN ALL LEACHING TRENCHES TO ALLOW SYSTEM MONITORING AND FLOW ADJUSTMENT AT THE FLOW SPLITER DISTRIBUTION BOX. USE HIGH LEVEL OVERFLOW DISTRIBUTION IN THE 3 NEW LEACHING TRENCHES.

### MINIMUM LEACHING SYSTEM SPREAD MLSS MLSS = HF X FF X PF

HF = HYDRAULIC FACTOR PF = PERCOLATION FACTOR

SOIL TEST PITS NO. 106 AND 107 LOCATED IN LEACHFIELD SYSTEM EXPANSION AREA DEPTH TO RESTRICTIVE LAYER: TEST PIT NO. 106 FIRM TO COMPACT SOIL 28 INCHES, FAINT MOTTLING 30 INCHES

TEST PIT NO. 108 FIRM TO COMPACT SOIL 24 INCHES, FAINT MOTTLING 28 INCHES USE RESTRICTIVE LAYER DEPTH OF 24 INCHES HYDRAULIC GRADIENT 10.8%

FF 2,400 GPD/300 GPD = 8 PF USE PERCOLATION RATE OF 10.1-20.0 MINUTES/INCH PERCOLATION TEST, PF = 1.25 SYSTEM SPREAD PROVIDED = 270 FT

### TEST PIT DATA

TOWN OF BOLTON LOCATION: ROSE FARM

MUNICIPALITY: BOLTON, CONNECTICUT

PROJECT NO.: 963-0014 TEST PITS 1-5 CONDUCTED ON APRIL 10, 2008 AND LOGGED BY JOSEPH M. DILLON, P.E.

### TEST PIT 1

VERY FIRM BROWN FINE SAND AND SILT, TRACE FINE GRAVEL DENSE BROWN FINE SAND, SOME SILT, LITTLE FINE GRAVEL (TILL)

MOTTLING 18" BEDROCK NONE BOULDERS 40"

### TEST PIT 2

COMPACT BROWN FINE SAND, SOME SILT, LITTLE FINE GRAVEL DENSELY COMPACTED BROWN FINE-MEDIUM SAND, SOME SILT, SOME FINE-MEDIUM

GRAVEL GWT 64" MOTTLING 12" BEDROCK NONE CORE SAMPLE 16"

### TEST PIT 3

BAG SAMPLE 18"

COMPACT BROWN FINE SAND, SOME SILT, LITTLE FINE-MEDIUM GRAVEL DENSELY COMPACTED BROWN FINE SAND, SOME SILT, LITTLE-SOME FINE-MEDIUM

### GWT 54" MOTTLING 18" BEDROCK NONE NESTED BOULDERS 0-36"

TEST PIT 4

### COMPACT BROWN FINE SAND AND SILT, LITTLE FINE-MEDIUM GRAVEL SANDY TILL GWT MOTTLING 16"

BEDROCK 88" TEST PIT 5

COMPACT BROWN FINE SAND WITH SILT, LITTLE FINE-MEDIUM GRAVEL DENSLY COMPACT TILL

GWT 54" MOTTLING BEDROCK

### SOIL PERCOLATION TEST DATA RECORD

OWNER: TOWN OF BOLTON

SITE ADDRESS: ROSE FARM, BOLTON CENTER ROAD, BOLTON CT

MUNICIPALITY: TOWN OF BOLTON

**DATE: APRIL 11, 2008** 

WEATHER: PERCOLATION TEST NO.:

DEPTH BELOW GROUND SURFACE: "

TIME OF PRESOAK: AM; HOLE DRY BY PM

Elapsed Time (min.)	Reference to water (in.)	Water Level Drop in Time Interval (in.)	Average Water Level Drop (min./in.)
	6.00	<b>-</b>	1 22 1 272
05:00		3.50	01:26
05:00	9.50	2.25	02:13
03,00	11.75	2.43	02,13
05:00	11,75	1.25	04:00
4	13.00		
05:00	VIA-2223. UN	1.00	05:00
0 202000	14.00		**************************************
05:00	1400	0.88	05:43
05:00	14.88	0.63	08:00
05.00	15.50	0.05	00,00
05:00		0.50	10:00
***************************************	16.00		
05:00		0,75	06:40
	16.75	<u> </u>	
05:00	17.13	0.38	13:20
05:00	17,13	0.50	10:00
05.00	17.63	0.50	10.00
05:00	100,100	0.38	13:20
	18.00		3.
05:00		0,50	10:00
	18,50		
	Time (min.)  05:00  05:00  05:00  05:00  05:00  05:00  05:00  05:00  05:00  05:00  05:00	Time (min.)  6.00  05:00  9.50  11.75  05:00  13.00  05:00  14.00  05:00  14.88  05:00  15.50  05:00  16.05  05:00  17.13  05:00  17.13	Time (min.) 6.00 3.50  05:00 9.50  05:00 11.75  05:00 12.25  11.75  05:00 13.00  05:00 14.00  05:00 0.88  14.88  05:00 15.50  05:00 0.50  16.00 0.75  16.75  05:00 0.38  17.13  05:00 17.63  05:00 0.38

TEST PERFORMED BY: JOSEPH M. DILLON, P.E.

COMMENTS

Nathan L. Jacobson & Associates, Inc. Chester Connecticut (203) 526-9591 PROGRESS PRINT DO NOT USE FOR CONSTRUCTION

FOR PRELIMINARY REVIEW ☐ FOR FINAL REVIEW

NOTES:

☐ FOR INFORMATION ONLY DATE ISSUED October 23, 2025

THIS DRAWING IS INTENDED TO BE USED FOR INFORMATION AND REVIEW URPOSES ONLY AND IS NOT INTENDED TO BE USED FOR CONSTRUCTION

NATHAN L. JACOBSON & ASSOCIATES

TOWN OF **BOLTON, CONNECTICUT** 

**TOWN CENTER** SUBSURFACE SEWAGE DISPOSAL

PROJECT NOTES AND SOIL INFORMATION

PERMITTING

ANY ALTERATIONS TO THIS DRAWING MADE WITHOUT THE EXPRESSED WRITTEN APPROVAL OF NATHAN L. JACOBSON & ASSOCIATES, INC. WILL BI AT THE SOLE RISK OF THE PERSON OR FIRM MAKING SUCH UNAUTHORIZE ALTERATIONS AND NATHAN L. JACOBSON & ASSOCIATES, INC. WILL NEITHE HAVE NOR ACCEPT ANY LIABILITY OR LEGAL EXPOSURE ARISING FROM SAI UNAUTHORIZED ALTERATIONS.



Nathan L. Jacobson & Associates, Inc. 86 Main Street P.O. Box 337 Chester, Connecticut 06412-0337 Tel: (860) 526-9591 Fax: (860) 526-5416 www.nlja.com Jacobson Consulting Civil and Environmental Engineers Since 1972


NOT VALID WITHOUT ORIGINAL SEAL JOSEPH M. DILLON, P.E.


© COPYRIGHT 2025 NATHAN L. JACOBSON & ASSOCIATES, INC. ALL RIGHTS RESERVED.


REVISIONS DESCRIPTION

DATE: JULY 202 SCALE: AS NOTED PROJECT No.: 09630053 CADD FILE: 09630053NOTES DESIGNED: BCC/JMI DRAWN: CEB CHECKED:

CT REGISTRATION No. 22903







### **List of Adjacent Properties**

### 206 Bolton Center Rd

206 Bolton Center Rd							
HANS CHRISTIAN ANDERSEN	212 BOLTON CENTER RD	BOLTON, CT 06043					
BOLTON TOWN OF	206 BOLTON CENTER RD	BOLTON, CT 06043					
220 Bc	olton Center Rd						
BOLTON TOWN OF	222 BOLTON CENTER RD	BOLTON, CT 06043					
LANE WILLIAM J & MICHELE L	17 TOOMEY RD	BOLTON, CT 06043					
BOLTON TOWN OF	222 BOLTON CENTER ROAD	BOLTON, CT 06043					
BOLTON CONGREGATIONAL CHURCH INC	228 BOLTON CENTER RD	BOLTON, CT 06043					
BOLTON CONGREGATIONAL CHURCH INC	228 BOLTON CENTER RD	BOLTON, CT 06043					
BOLTON TOWN OF	222 BOLTON CENTER ROAD	BOLTON, CT 06043					
BEEBE REBECCA	21 TOOMEY RD	BOLTON, CT 06043					
222 Bo	olton Center Rd						
BOLTON TOWN OF	222 BOLTON CENTER RD	BOLTON, CT 06043					
BOLTON CONGREGATIONAL CHURCH INC	228 BOLTON CENTER RD	BOLTON, CT 06043					
BOLTON CONGREGATIONAL CHURCH INC	228 BOLTON CENTER RD	BOLTON, CT 06043					
BOLTON TOWN OF	222 BOLTON CENTER ROAD	BOLTON, CT 06043					
266 Bc	olton Center Rd						
HULL THOMAS	19 MAPLE VALLEY RD	BOLTON, CT 06043					
HANLON ALEXANDRA	84 MAPLE VALLEY RD	BOLTON, CT 06043					
ROSE RICHARD L & MARY ANN	18 STEELES CROSSING RD	BOLTON, CT 06043					
ASPINALL KATHLEEN ROSE & DANA P	6 STEELES CROSSING RD	BOLTON, CT 06043					
SCHERR JOSEPH D & SHERR KATHLEEN M	280 BOLTON CENTER RD	BOLTON, CT 06043					
BOLTON TOWN OF	222 BOLTON CENTER ROAD	BOLTON, CT 06043					
BOLTON TOWN OF	222 BOLTON CENTER ROAD	BOLTON, CT 06043					
BEEBE REBECCA	21 TOOMEY RD	BOLTON, CT 06043					
GUDAUSKAS RANDY W & ANDREA R	27 MAPLE VALLEY RD	BOLTON, CT 06043					
KEELER MICHAEL D	88 MAPLE VALLEY RD	BOLTON, CT 06043					
PROTSAILO LESIA V & BOKSHAN EVAN TARAS	78 MAPLE VALLEY RD	BOLTON, CT 06043					
CLAVET MARCEL G & SANDRA L	70 MAPLE VALLEY RD	BOLTON, CT 06043					
CONNECTICUT STATE OF	79 ELM ST	HARTFORD, CT 06106					

Report: All unexpired permits for which the permitted activities have not been completed

			Expiration	Work	Active	Fully		
Record #	Applicant Name	Address	Date	started?	work?	stabilized?	Brief Project Description	Agent Permit?
IW-25-15	Brian Werhle	74 Cider Mill	9/12/2027	Yes	Yes	No	ADU and driveway extension	Yes
IW-25-14	Ronald Bisson	139 Vernon	9/30/2027	No	No	Yes	Select tree cutting	No
IW-25-13	Jordan Knight	51 Loomis	9/25/2027	Yes	No	Yes	Construction of duplex	No
IW-25-12	Noah Ludecke	44 Notch	8/28/2027	Yes	Yes	Yes	Removal of invasives	Yes
IW-25-11	Town of Bolton	87 Brandy St	8/28/2027	Yes	Yes	No	Installation of drainage pipe	No
IW-25-7	Eric Peterson	61 VERNON RD, BOLTON, CT 06043	7/8/2027	No	No	Yes	Single-family home construction	No
IW-25-6	Edith Bodman	45 VERNON RD, BOLTON, CT 06043	5/30/2027	Yes	Yes	Yes	Single-family home on existing foundation	Yes
IW-25-4	Bryan Fairclough	148 BRANDY ST, BOLTON, CT 06043	5/8/2027	Yes	No	Yes	In-ground heated pool and sport court	Yes
IW-25-3	James Read	0 VERNON RD, BOLTON, CT 06043	3/4/2027	No	No	Yes	Single-family cottage construction	No

Not started Active

Recently completed: IW-20-5 - Fabio Koellmer - 1 Notch Rd