

- Remove urinals and seal off plumbing.
- Remove urinal separator walls.
- Remove steam pipe insulation.

Restroom 2 (Marked C on Floor Plan)

- Remove and discard existing toilet, stall walls and doors.
- Remove one vanity ~~for use in Restroom 1.~~
- Remove steam pipe insulation.

Custodian Closet (Marked A on Floor Plan)

- Remove all built in shelves.
- Remove utility sink.
- Remove carpeting.
- Remove old electrical outlet.
- Remove light fixture.

Storage Closet (Marked D on Floor Plan)

- Remove all non-code electrical fixtures.

Contractor to demo classroom 1, classroom 2 and classroom 3 and classroom closets to perform isolated remodel per plans.

Classroom 1

- Remove all data ports, wiring and trays. Data cables that are routed through Classroom 1 to other areas of the building to remain.
- Remove steam pipe insulation.

Classroom 2

- Remove built in shelves on east wall.
- Remove built in shelves on south wall.
- Remove built in display board on north wall.
- Remove steam pipe insulation.

Classroom 3

- Remove drop ceiling and light fixtures.
- Remove duct work above drop ceiling.
- Demo wall switches and electrical in partition walls.
- Demo internal walls per plans.
- Remove all wall paneling.
- Demo display boards on west and east walls.
- Remove steam pipe insulation.

Classroom 1 Closet (Marked E on floor plan)

- Remove all built in shelves.
- Remove all non-code electrical fixtures.